

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8361	05-00083-08-SF	EFFINGHAM	40	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

SFTY-18

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20800150	TRENCH BACKFILL	CU YD	6.8
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	785
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	1.3
28000300	TEMPORARY DITCH CHECKS	EACH	7
28000400	PERIMETER EROSION BARRIER	FOOT	3,205
28000500	INLET AND PIPE PROTECTION	EACH	14
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	950
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	34,560
42400800	DETECTABLE WARNINGS	SQ FT	48
* 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	72
* 550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	4
* 550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	41
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	6
60260100	INLETS TO BE ADJUSTED	EACH	1
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
67100100	MOBILIZATION	L SUM	1
Δ * 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
Δ * 80400200	ELECTRIC UTILITY SERVICE CONNECTION	LS	1
Δ 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	30
Δ * 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	50
Δ * 81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	450
Δ * 81400400	CONCRETE HANDHOLE	EACH	1
Δ 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,300
Δ 81700130	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE RHW) 1/C NO. 2	FOOT	140
Δ 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	10
Δ 82500510	LIGHTING CONTROLLER TYPE CB-RCS 60AMP - 240VOLT	EACH	1
Δ 83000500	LIGHT POLE, ALUMINUM, 30 FT. M.H., 12 FT. DAVIT ARM	EACH	10
Δ 83600350	LIGHT POLE FOUNDATION METAL, 1" BOLT CIRCLE, 8" X6"	EACH	10
Δ * XX003763	UNIT DUCT, WITH 4-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIAMETER POLYETHYLENE	FOOT	1,500
Δ * X8160165	UNIT DUCT, WITH 2-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (EPR-TYPE RHW), 1 1/4" DIAMETER POLYETHYLENE	FOOT	246

* SEE SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT.
 HORIZ.
 DATE 03/24/06

DRAWN BY JAP
 CHECKED BY JTB



Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

LAYOUT: JTB 03/24/06
 DRAWN: JTB 03/24/06
 REVIEWED: JTB 03/24/06
 PLOT DATE: 03/24/06 10:50 AM
 FILE NAME: I:\06\hans\proj\2006\code\road\Sheet\SheetVC-601.dgn
 PLOT SCALE: 50:8000 / IN.
 USER NAME: Jap