

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9315	00-00032-00-RP	MONROE	49	3
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 97264				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN - MONROE COUNTY	
			FEDERAL 75% CITY 25%	TOTAL QUANTITY
				J000-2A
20200100	EARTH EXCAVATION	CU. YD.		1268
20400800	FURNISHED EXCAVATION	CU. YD.		421
20900110	POROUS GRANULAR BACKFILL	CU. YD.		1477
20900330	GRANULAR BACKFILL	TON		81
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO. YD.		1083
25000110	SEEDING, CLASS 1A	ACRE		0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND		27
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND		27
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND		27
25000700	AGRICULTURAL GROUND LIMESTONE	TON		0.6
25101005	HEAVY DUTY EXCELSIOR BLANKET	SO. YD.		1225
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND		30
28000400	PERIMETER EROSION BARRIER	FOOT		158
28100705	STONE DUMPED RIPRAP, CLASS A3	SO. YD.		813
28200200	FILTER FABRIC	SO. YD.		813
31100300	SUBBASE GRANULAR MATERIAL, TYPE A, 4"	SO. YD.		2573
31100700	SUBBASE GRANULAR MATERIAL, TYPE A, 8"	SO. YD.		225
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SO. YD.		754
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON		281
40600300	AGGREGATE (PRIME COAT)	TON		2
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SO. YD.		1571
42001300	PROTECTIVE COAT	SO. YD.		2175
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO. YD.		203
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO. FT.		1743
42400800	DETECTABLE WARNINGS	SO. FT.		150
44000100	PAVEMENT REMOVAL	SO. YD.		252
44000600	SIDEWALK REMOVAL	SO. FT.		85
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH		1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH		1
50300225	CONCRETE STRUCTURES	CU. YD.		27.4
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND		2070
51500100	NAME PLATES	EACH		1
54000900	BOX CULVERT END SECTIONS, SPECIAL	EACH		1
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH		3
54021006	PRECAST CONCRETE BOX CULVERT 10'x6' (M273)	FOOT		376.2
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT		54
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT		64
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT		12
55100500	STORM SEWER REMOVAL 12"	FOOT		51
60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SO. YD.		96
60100915	PIPE DRAINS 6"	FOOT		50
60101805	PIPE DRAINS 8" (SPECIAL)	FOOT		8
60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH		1
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH		2
60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH		2
60500060	REMOVING INLETS	EACH		1
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT		744
67100100	MOBILIZATION	L. SUM		1
70101700	TRAFFIC CONTROL AND PROTECTION	L. SUM		1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM		1
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT		500
78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT		1488
78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT		63
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON		360
Z0073500	TEMPORARY SUPPORT SYSTEM	L. SUM		1
X0321865	ANTI-GRAFFITI PROTECTION SYSTEM	SO. FT.		2746
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT		24
X0323410	TRIANGULAR SILT DIKES	EACH		4
X0330200	SANITARY MANHOLES TO BE ADJUSTED	EACH		3
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON		76
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON		236
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH		8
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH		2
XX006534	SANITARY SEWER, PVC, 10" IN 16" CASING PIPE	L. SUM		1

* SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE _____ DRAWN BY _____
 DATE _____ CHECKED BY _____

CADD FILE: A6907/FBsmg_4690.dgn
 PLOTTED: 8/24/18

H.M. & G. INC. 4690