



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2006

SUBJECT: Route S.B.I. 1 (Old Rte. 13/IL 127)
Section Pavement Preservation FY 06
Gallatin/Perry Counties
Contract No. 98933
Item No. 45, June 26, 2006 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page iii of the Table of Contents to the Special Provisions.
2. Revised page 52 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.", with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 9; Roger Driskell; Estimates; Design & Environment File

TBW:DB:jc

TABLE OF CONTENTS

LOCATION OF PROJECT 1
DESCRIPTION OF PROJECT 1
UTILITIES 1
TRAFFIC CONTROL PLAN 2
PILOT CAR 3
MICRO-SURFACING (BMPR) 3
CAPE SEAL (BMPR) 14
BITUMINOUS SURFACE TREATMENTS (PREVENTIVE MAINTENANCE) (BMPR) 27
AGGREGATE SHIPPING TICKETS (BDE) 33
BITUMINOUS EQUIPMENT, SPREADING AND FINISHING MACHINE (BDE) 33
FLAGGER VESTS (BDE) 34
PARTIAL PAYMENTS (BDE) 34
PAYMENTS TO SUBCONTRACTORS (BDE) 35
PAYROLLS AND PAYROLL RECORDS (BDE) 36
PERSONAL PROTECTIVE EQUIPMENT (BDE) 37
POLYMER MODIFIED EMULSIFIED ASPHALT (BDE) 38
RAP FOR USE IN BITUMINOUS CONCRETE MIXTURES (BDE) 38
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 42
SUPERPAVE BITUMINOUS CONCRETE MIXTURES (BDE) 42
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 48
TRUCK BED RELEASE AGENT (BDE) 49
WEIGHT CONTROL DEFICIENCY DEDUCTION 49
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 51
WORKING DAYS (BDE) 52
DELAY START-UP AT LOCATION #1 52

Revised 06/07/2006

Add the following to Article 702.03 of the Standard Specifications:

“(h) Vertical Barricades. Vertical barricades may be used in lieu of cones, drums or Type II barricades to channelize traffic.”

Delete the fourth paragraph of Article 702.05(a) of the Standard Specifications.

Revise the sixth paragraph of Article 702.05(a) of the Standard Specifications to read:

“When the work operations exceed four days, all signs shall be post mounted unless the signs are located on the pavement or define a moving or intermittent operation. When approved by the Engineer, a temporary sign stand may be used to support a sign at 1.2 m (5 ft) minimum where posts are impractical. Longitudinal dimensions shown on the plans for the placement of signs may be increased up to 30 m (100 ft) to avoid obstacles, hazards or to improve sight distance, when approved by the Engineer. “ROAD CONSTRUCTION AHEAD” signs will also be required on side roads located within the limits of the mainline “ROAD CONSTRUCTION AHEAD” signs.”

Delete all references to “Type 1A barricades” and “wing barricades” throughout Section 702 of the Standard Specifications.

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within 25 working days.

DELAY START-UP AT LOCATION #1

Due to another project with an earlier start-up at Location 1, Old Shawneetown location, work cannot begin at this location until after the date of September 1, 2006. At the contractors option, the start-up of the entire project may be delayed until September 1, 2006.

Revised 06/07/2006