

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	60	4

STA. _____ TO STA. _____
 FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT

* CX1-(4,4-1,5,6,6-2) R-1

SUMMARY OF QUANTITIES

SHEET 1 OF 3

CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	90% FEDERAL / 10% STATE	
			TOTAL QUANTITY	ROADWAY I 000
78003135	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 6", SPECIAL	FOOT	10108	10108
X0300471	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SOYD	100035	100035
* X0300780	PIEZO ELECTRIC AXLE SENSOR CABLE IN CONDUIT	FOOT	465	465
X0322729	MATERIAL TRANSFER DEVICE	TON	52894	52894
X0322278	RODENT SHIELDS	EACH	8	8
* X0323014	ELECTRIC CABLE IN CONDUIT, CONOGA-30003	FOOT	840	840
* X0323015	PIEZO ELECTRIC AXLE SENSOR, CLASS II	FOOT	14	14
X4066540	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N105	TON	12698	12698
X4066660	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	TON	45254	45254
* X6330115	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL, REMOVE AND RELOCATE	EACH	2	2
* X6330200	VERTICAL ADJUSTMENT OF TRAFFIC BARRIER TERMINAL	EACH	3	3
* X0325412	REMOVE AND REPLACE STEEL PLATE BEAM GUARDRAIL, SPECIAL	FOOT	850	850
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	70	70
△ Z0030250	IMPACT ATTENUATOR TEMPORARY NON-REDIRECTABLE TL3	EACH	5	5
△ Z0030350	IMPACT ATTENUATOR RELOCATE NON-REDIRECTABLE TL3	EACH	5	5
25000350	SEEDING, CLASS 7	ACRE	1.25	1.25
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	198	198
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	148	148
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	148	148
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.5	2.5
25001010	SEEDING, CLASS 2 (MODIFIED)	ACRE	1.25	1.25
25100115	MULCH, METHOD 2	ACRE	2.5	2.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	247	247
28000300	TEMPORARY DITCH CHECKS	EACH	6	6
28102600	STONE RIPRAP DITCH	TON	880	880
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	8006	8006
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	54139	54139
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	4713	4713
40600990	TEMPORARY RAMP	SQ YD	1063	1063
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	469	469
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	1609	1609
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	101425	101425
44000100	PAVEMENT REMOVAL	SQ YD	5624	5624
44004250	PAVED SHOULDER REMOVAL	SQ YD	5201	5201

* SPECIALTY ITEM
 △ INDICATES CONSTRUCTION TYPE CODE SFTY-3N

PLOT DATE = 4/17/2006
 PLOT SCALE = 50.0000' / IN.
 USER NAME = bboomer1

Rev.