CONTRACT NO. 98948

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	WILLIAMSON	60	13
STA. _____ TO STA._____				
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

* [X1-(4,4-1,5,6,6-2)] R-1

SEEDING AND EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	SEEDING CLASS 2 (MODIFIED)	SEEDING CLASS 7 (TEMPORARY)	NITROGEN FERTILIZER NUTRIENTS CLASS 2	NITROGEN FERTILIZER NUTRIENTS CLASS 7	PHOSPHORUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	AGRICULTURAL GROUND LIMESTONE	MULCH METHOD 2 FOR CLASS 2	MULCH METHOD 2 FOR CLASS 7	TEMPORARY EROSION CONTROL SEEDING	TEMPORARY DITCH CHECKS
	ACRE	ACRE	POUND	POUND	POUND	POUND	TON	ACRE	ACRE	POUND	EACH
NORTHBOUND											
67+72 TO 70+11	0.19	0.19	22.6	7.5	22.6	22.6	0.4	0.19	0.19	37.7	1
192+00 TO 194+05	0.16	0.16	19.8	6.6	19.8	19.8	0.3	0.16	0.16	33.0	1
235+26 TO 238+40	0.24	0.24	28.8	9.6	28.8	28.8	0.5	0.24	0.24	48.0	1
325+37 TO 328+08	0.21	0.21	25.2	8.4	25.2	25.2	0.4	0.21	0.21	42.1	1
389+18 TO 393+33	0.31	0.31	37.1	12.4	37.1	37.1	0.6	0.31	0.31	61.9	1
407+09 TO 408+49	0.12	0.12	14.4	4.8	14.4	14.4	0.2	0.12	0.12	24.0	1
TOTALS	1.25	1.25	148	50	148	148	2.5	1.25	1.25	247	6
			198					2.50			

NOTES:
SEEDING QUANTITIES ARE CALCULATED FOR 15' AROUND THE PERIMETER FOR ALL PAVED DITCH REMOVALS.
THE ACTUAL LOCATIONS SHALL BE AS DIRECTED BY THE ENGINEER.

STONE RIPRAP DITCH

LOCATION STATION TO STATION	LENGTH OF STONE RIPRAP DITCH (SEE NOTE)	STONE RIPRAP DITCH
	FOOT	TON
NORTHBOUND		
67+72 TO 70+11	239	133
192+00 TO 194+05	205	114
235+26 TO 238+40	314	174
325+37 TO 328+08	271	151
389+18 TO 393+33	415	231
407+09 TO 408+49	140	78
TOTAL		880

NOTE: NOT A PAY ITEM - FOR INFORMATION ONLY

TEMPORARY BARRIER SCHEDULE

LOCATION STATION TO STATION	LENGTH (FOR INFORMATION ONLY)	IMPACT ATTENUATOR (TEMPORARY)	IMPACT ATTENUATOR (RELOCATE)	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
	FEET	EACH	EACH	FEET	FEET
NORTHBOUND					
79+25 TO 85+39	614	1	1	625.0	625.0
163+15 TO 169+79	664	1	1	675.0	675.0
226+05 TO 233+30	725	1	1	725.0	725.0
252+85 TO 258+94	609	1	1	612.5	612.5
361+25 TO 366+99	574	1	1	575.0	575.0
TOTALS	3186	5	5	3212.5	3212.5

MEDIAN CROSSOVER SCHEDULE

LOCATION STATION	INCIDENTAL BITUMINOUS SURFACE	BITUMINOUS MATERIALS PRIME COAT	AGGREGATE SHOULDERS TYPE B	TEMPORARY RAMP	BIT SURFACE REMOVAL BUTT JOINT
	TONS	GAL	TONS	SQ YD	SQ YD
NORTHBOUND					
7+90	56	27	9	30	132
135+75	103	51	9	62	255
196+34	105	52	9	65	264
305+91	103	51	9	62	252
409+20	102	51	9	61	255
TOTALS	469	232	43	279	1157

PIPE UNDERDRAIN SCHEDULE

LOCATION STATION TO STATION	PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALL FOR PIPE DRAINS	RODENT SHIELD	REMARKS
	FOOT	FOOT	EACH	EACH	
NORTHBOUND					
79+50 TO 83+70	840	42	2	2	TR 23 OVERPASS
163+40 TO 168+10	940	42	2	2	FAS 903 OVERPASS
253+10 TO 257+25	830	42	2	2	FAS 2903 OVERPASS
361+50 TO 365+30	760	42	2	2	FAU 9624 OVERPASS
TOTALS	3370	168	8	8	

NOTE: TRENCH BACKFILL FOR PIPE UNDERDRAINS SHALL BE INCLUDED IN THE COST OF PIPE UNDERDRAINS.

PLOT DATE = 4/17/2006
FILE NAME = c:\pw_pw1\d-1\98948\sheets\98948sch.h32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = thomasbf

SEEDING AND EROSION CONTROL, STONE RIPRAP, TEMPORARY BARRIER, MEDIAN CROSSOVER, AND PIPE UNDERDRAIN SCHEDULES (I-57 MAINLINE)