

### SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	RWY END 2 REMOVAL QUANTITIES	TWY A & C WIDENING QUANTITIES	TWY A QUANTITIES	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	1,457	7,014	6,092	14,563	
AR108554	2/C #4 600 V UG CABLE IN UD	L.F.	0	0	1,091	1,091	
AR108558	2/C #8 600 V UG CABLE IN UD	L.F.	251	0	0	251	
AR110014	4" DIRECTIONAL BORE	L.F.	560	0	0	560	
AR110502	2-WAY CONCRETE ENCASED DUCT	L.F.	56	0	153	209	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	280	0	0	280	
AR110552	EXTEND 2-WAY DUCT	L.F.	0	66	0	66	
AR110554	EXTEND 4-WAY DUCT	L.F.	0	30	0	30	
AR110714	ELECTRIC MANHOLE 4'	EACH	3	0	0	3	
AR110900	REMOVE DUCT	L.F.	0	0	82	82	
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	0	0	1	1	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	0	0	1	1	
AR125447	TAXI GUIDANCE SIGN, 7 CHARACTER	EACH	0	1	0	1	
AR125470	MODIFY EXISTING SIGN PANEL	EACH	0	0	1	1	
AR125565	SPLICE CAN	EACH	0	0	3	3	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	2	0	2	4	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	2	1	1	4	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	0	0	2	2	
AR125950	ADJUST PLASI	EACH	1	0	0	1	
AR125961	RELOCATE STAKE MOUNTED LIGHT	EACH	22	55	34	111	
AR125962	RELOCATE BASE MOUNTED LIGHT	EACH	2	7	2	11	
AR125964	RELOCATE TAXI GUIDANCE SIGN	EACH	1	3	2	6	
AR125967	RELOCATE REILS	PAIR	1	0	0	1	
AR125968	RELOCATE PAPI	EACH	1	0	0	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	0	0	0	1	
AR150540	HAUL ROUTE	L.S.	0	0	0	1	
AR151450	CLEARING AND GRUBBING	ACRE	0.2	0	0	0.2	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	44,355	6,812	34,621	85,788	
AR152441	ON-SITE BORROW	C.Y.	1,126	0	2,976	4,102	
AR156510	SILT FENCE	L.F.	1,497	0	500	1,997	
AR156511	DITCH CHECK	EACH	0	0	2	2	
AR156513	SEPARATION FABRIC	S.Y.	5,948	9,833	6,078	21,859	
AR156520	INLET PROTECTION	EACH	2	1	3	6	
AR156521	HEADWALL PROTECTION	EACH	0	6	1	7	
AR156530	TEMPORARY SEEDING	ACRE	28.4	8.5	16.0	52.9	
AR156544	RIPRAP-GRADATION NO. 4	S.Y.	0	45	192	237	
AR161616	CLASS C GATE - 16'	EACH	1	0	0	1	
AR201610	BITUMINOUS BASE COURSE	TON	704	3,126	2,017	5,847	
AR201630	BITUMINOUS BASE TEST SECTION	EACH	0	1	0	1	
AR208540	OVERSIZED AGGREGATE	TON	802	3,604	2,311	6,717	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	2,718	3,219	2,871	8,808	
AR401610	BITUMINOUS SURFACE COURSE	TON	242	1,007	667	1,916	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	0	42	0	42	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	0	5,568	0	5,568	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	5,730	42	4,165	9,937	
AR602510	BITUMINOUS PRIME COAT	GAL.	761	4,682	2,119	7,562	
AR603510	BITUMINOUS TACK COAT	GAL.	613	2,719	1,754	5,086	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	41,018	8,712	3,875	53,605	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	0	8,029	46	8,075	
AR620912	TEMPORARY MARK & LIGHT	L.S.	0	0	0	1	
AR701518	18" RCP, CLASS IV	L.F.	0	53	0	53	
AR701524	24" RCP, CLASS IV	L.F.	0	0	402	402	
AR701530	30" RCP, CLASS IV	L.F.	0	26	303	329	
AR701536	36" RCP, CLASS IV	L.F.	0	67	136	203	
AR701548	48" RCP, CLASS IV	L.F.	0	0	116	116	
AR701612	12" RCP, CLASS V	L.F.	0	0	1,418	1,418	
AR701900	REMOVE PIPE	L.F.	0	0	180	180	
AR705410	POROUS BACKFILL	C.Y.	32	197	167	396	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	L.F.	876	5,307	2,644	8,827	
AR705546	6" NON PERFORATED UNDERDRAIN	L.F.	0	0	100	100	
AR705548	8" NON PERFORATED UNDERDRAIN	L.F.	0	0	100	100	
AR705550	10" NON PERFORATED UNDERDRAIN	L.F.	0	0	100	100	
AR705630	UNDERDRAIN INSPECTION HOLE	EACH	4	14	11	29	
AR705900	REMOVE UNDERDRAIN	L.F.	1,587	5,395	0	6,982	
AR705903	REMOVE UNDERDRAIN INSP. HOLE	EACH	5	10	9	24	
AR751411	INLET-TYPE B	EACH	0	0	1	1	
AR751540	MANHOLE 4'	EACH	0	0	1	1	
AR751944	ADJUST MANHOLE - PAVEMENT	EACH	0	0	2	2	
AR751945	ADJUST MANHOLE - NON PAVEMENT	EACH	0	0	5	5	
AR752430	PRECAST REINFORCED CONC. FES 30"	EACH	0	0	1	1	
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	0	0	4	4	
AR752618	CONCRETE HEADWALL 18"	EACH	0	2	0	2	

### SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	RWY END 2 REMOVAL QUANTITIES	TWY A & C WIDENING QUANTITIES	TWY A QUANTITIES	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR752630	CONCRETE HEADWALL 30"	EACH	0	1	0	1	
AR752636	CONCRETE HEADWALL 36"	EACH	0	2	0	2	
AR752648	CONCRETE HEADWALL 48"	EACH	0	0	1	1	
AR752903	REMOVE HEADWALL	EACH	0	5	2	7	
AR770516	16" DUCTILE IRON SANITARY SEWER	L.F.	0	0	410	410	
AR770704	SANITARY MANHOLE 4'	EACH	0	0	1	1	
AR770905	REMOVE SANITARY MANHOLE	EACH	0	0	1	1	
AR770945	ADJUST SANITARY MANHOLE	EACH	0	0	1	1	
AR800405	INSTALL TEMPORARY LIGHTING	L.S.	0	0	0	1	
AR800429	FIELD TILE TRACING	EACH	0	0	6	6	
AR800463	FILED TILE REPAIR	EACH	0	0	6	6	
AR901510	SEEDING	ACRE	28.2	7.5	15.6	51.3	
AR901550	LIME AND FERTILIZER	ACRE	0	0	3.8	3.8	
AR908510	MULCHING	ACRE	28.1	6.6	15.2	49.9	
AR908520	EXCELSIOR BLANKET	S.Y.	947	4,771	2,149	7,867	

DK050

MAY 15, 2006 3:14 PM CAH  
I:\AIRPORTS\DEKALB\003-0517\AIRPORT SHEETS\GENERAL\R-002\F.P.DWG

DATE	
REVISION	
BY	

**DIMAX**  
DEKALB TAYLOR MUNICIPAL AIRPORT  
IL PROJ.: DKB-3448 AIP PROJ.: 3-17-0139-843

U.S. Project No.	80305TXAD 0800
Envelope	R-002.F.P.DWG
Scale	N/A
Date	12/28/05
LAYOUT	MDR 12/25/05
DRAWN	MDR 12/28/05
REVIEWED	CAH 03/08/06

**HANSON**  
Hanson Professional Services Inc.  
1525 South Sixth Street  
Springfield, Illinois 62703-2886  
Offices Nationwide

DEKALB AIRPORT  
IMPROVEMENTS  
SUMMARY OF QUANTITIES