

TAXIWAY "A" CONTROL POINTS		
POINT NO	NORTHING	EASTING
1	1,917,654.0730	882,636.9614
2	1,917,653.0828	883,060.2791
3	1,917,651.9372	883,548.7406

REMOVE BITUMINOUS PAVEMENT

THE AREA DESIGNATED AS [Hatched Box] ON THIS SHEET WILL HAVE THE EXISTING PAVEMENT REMOVED (FULL DEPTH) TO A SUITABLE SUBGRADE. ALL REMOVED BITUMINOUS MATERIAL WILL BE DISPOSED OF OFF THE AIRPORT SITE. THE AGGREGATE BASE WILL BE USED IN FILL AREAS.


WHERE THE PROPOSED REMOVAL AREA ABUTTS THE EXISTING PAVEMENT, THE PAVEMENT WILL BE SAWED AS SHOWN ON THIS SHEET. THE SAWING WILL BE CONSIDERED AS AN INCIDENTAL ITEM TO THE PROPOSED PAVEMENT REMOVAL AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ANY ADJACENT PAVEMENT DAMAGED BY THE PAVEMENT REMOVAL OPERATIONS WILL BE REPAIRED AT THE CONTRACTOR'S OWN EXPENSE.

THE REMOVAL OF BITUMINOUS PAVEMENT WILL BE PAID FOR UNDER ITEM:
AR401900 "REMOVE BITUMINOUS PAVEMENT" _____ 4,165 SQ. YDS.

LEGEND

- [Solid Box] EXISTING PAVEMENT
- [Hatched Box] EXISTING PAVEMENT (TO BE REMOVED)
- [Dotted Box] PROPOSED PAVEMENT
- [Line with Saw Notation] EXISTING DUCT (TO BE REMOVED)



0' 25' 50' 100'
 HALF SIZE SCALE: 1" = 100'
 FULL SIZE SCALE: 1" = 50'

DATE	REVISION	BY



IL PROJ.: DK8-3448 A.I.P. PROJ.: 3-17-0139-B42

HE Project No. 803-051XAD_0800	
Plan No. R-121CON.DWG	
Scale 1" = 50'	
Date 01/18/06	
LAYOUT J.E.O. 01/18/06	
DRAWN B.A.K. 01/18/06	
REVIEWED C.A.H. 02/22/06	



Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62705-2886
 Offices Nationwide

EXTEND TAXIWAY "A"
PROPOSED CONSTRUCTION PLAN FOR TAXIWAY "A"
 STA. 129+80.84 TO STA. 139+00