

NOTE:

QUANTITY OF MARKING REMOVAL ON THIS SHEET - 1,382 S.F.

620900-PAVEMENT MARKING REMOVAL NOTES

THE EXISTING PAVEMENT MARKING SHALL BE REMOVED IN ACCORDANCE WITH ITEM 620 "PAVEMENT MARKING" AS STATED ON PAGE 77 OF THE SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS, ADOPTED JULY 1, 2004.


THE AREAS THAT ARE DESIGNATED FOR REMOVAL ARE SHOWN ON THE CONSTRUCTION PLANS.

ALL AREAS TO BE REMOVED ARE CALCULATED AREAS. ANY ADDITIONAL AREAS, DUE TO OVER SPRAY, SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

THE PROPOSED MARKING REMOVAL WILL BE PAID FOR UNDER ITEM:
AR620900 PAVEMENT MARKING REMOVAL ____ 8,029 S.F.

LEGEND

- EXISTING PAVEMENT
- EXISTING MARKING (TO BE REMOVED)
- EXISTING MARKING (TO REMAIN)
- PROPOSED PAVEMENT



DATE	REVISION	BY



PROJ.: DKB-3448 AIP PROJ.: 3-17-0139-B42

NPS Project No. 80305XXAD_0800 Filename R-152MRK.DWG Scale 1" = 50' Date 01/05/05	LAYOUT JMB 01/05/05 DRAWN JMB 01/05/05 REVIEWED CAH 02/22/06
--	--



WIDEN TAXIWAYS A & C FROM 35' TO 50'

EXISTING MARKING REMOVAL PLAN STA. 102+00 TO STA. 111+00