URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80/20 (FED/STATE) ROADWAY 0005				
CODE NO	ITEM	UNIT						
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3				
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	47	47 △				
* 66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1				
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4 △				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	LSUM	1	1				
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LSUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LSUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	LSUM	1	1				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	5379	5379				
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2690	2690				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	155	155				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16149	16149				

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80/20 (FED/STATE) ROADWAY 005				
CODE NO	ITEM	UNIT						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1086	1086				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	186	186				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	290	290				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	2690	2690				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	155	155				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16149	16149				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1616	1616				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	186	186				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	290	290				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	532	532				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	532	532				
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	7	7				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1533	1533				
* 89502376	REBUILD EXISTING HANDHOLE	EACH	13	13				

* SPECIALTY ITEMS
△ NON-PARTICIPATION ITEMS

FILE NAME =	USER NAME = dlatta	DESIGNED -	REVISED -
pw:\\LDBAED\DINTEG\Infolgen\PW\DGN\Documents\000	Offices\District NProjects\D05210\CADData\Design\D05C05DR.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 4/6/2017	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
25TH AVENUE (GRAND AVENUE TO ARMITAGE AVENUE)

SCALE: NONE | SHEET NO. 2 OF 3 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2714	(3198C&D)RS-3	COOK	34	4

CONTRACT NO. 62A01

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

△ Rev 6-5-17