

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE	0005 100% VILLAGE OF MOUNT PROSPECT		
20200100	EARTH EXCAVATION	CU YD	95	95			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2431	2431			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10			
25200110	SODDING, SALT TOLERANT	SO YD	2674	2674			
25200200	SUPPLEMENTAL WATERING	UNIT	94	94			
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	9	9			
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SO YD	20	20			
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	64110	64110			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	143	143			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	3920	3920			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	700	700			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4	4			

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE	0005 100% VILLAGE OF MOUNT PROSPECT		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7977	7977			
42001300	PROTECTIVE COAT	SO YD	3236	3236			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	300	300			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	108	108			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	9611	9611			
42400800	DETECTABLE WARNINGS	SO FT	868	868			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	94965	94965			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	437	437			
44000600	SIDEWALK REMOVAL	SO FT	8869	8869			
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	75	75			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	1709	1709			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	250	250			
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	250	250			

\* = SPECIALTY ITEMS

FILE NAME: p:\NLD\BIB\DI\EG\I\rd\sp\PW\DOT\Documents\5007	USER NAME: e\delman	DESIGNED: -	REVISED: -
Offices\District\NPR\delman\DM2146\CA00\delman\DM2146		CHECKED: -	REVISED: -
PLOT SCALE: 1/4" = 100.0000'		DATE: -	REVISED: -
PLOT DATE: 3/31/2011			

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
IL RTE 83 (ELMHURST RD) - US RTE 14 TO 0.1-MI S OF PALATINE RD

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 344	SECTION (978&3192)RS-2	COUNTY COOK	TOTAL SHEETS 54	SHEET NO. 4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CONTRACT NO. 62009				

Rev 6-5-17

Rev

