



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2017

SUBJECT: FAP Route 344 (IL 83)
Project NHPP-0344(064)
Section (524-1&2)RS
Cook County
Contract No. 60L98
Item No. 158, June 16, 2017 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised page ii of the Table of Contents to the Special Provisions
3. Added page 93 to the Special Provisions
4. Revised sheet 5 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' followed by a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Anthony Quigley, Region 1, District 1; Tim Kell; Estimates

MS/ck

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60L98

State Job # - C-91-065-11

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - (524-1&2) RS

Project Number

NHPP-0344/064/

*REVISED: JUNE 05, 2017

Route

FAP 344

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322936	REMOV EX FLAR END SEC	EACH	3.000				
X0326763	REMOVE GRATING	EACH	1.000				
X2020110	GRADING & SHAP SHLDRS	UNIT	238.500				
X4021000	TEMP ACCESS- PRIV ENT	EACH	1.000				
X4400100	PCC SURF REM VAR DP	SQ YD	2,222.000				
X5537800	SS CLEANED 12	FOOT	350.000				
X6030310	FR & LIDS ADJUST SPL	EACH	10.000				
X7030005	TEMP PAVT MKING REMOV	SQ FT	33,473.000				
Z0004562	COMB C C&G REM & REPL	FOOT	964.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018500	DRAINAGE STR CLEANED	EACH	35.000				
Z0030850	TEMP INFO SIGNING	SQ FT	102.800				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
Z0064800	SELECTIVE CLEARING	UNIT	85.800				
Z0076600	TRAINEES	HOURL	500.000		0.800		400.000

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60L98

State Job # - C-91-065-11

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - (524-1&2) RS

Project Number

NHPP-0344/064/

*REVISED: JUNE 05, 2017

Route

FAP 344

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0076604	TRAINEES TPG	HOUR	500.000		15.000		7,500.000
20200100	EARTH EXCAVATION	CU YD	253.000				
20201200	REM & DISP UNS MATL	CU YD	50.000				
20800150	TRENCH BACKFILL	CU YD	186.000				
21101615	TOPSOIL F & P 4	SQ YD	160.000				
21101625	TOPSOIL F & P 6	SQ YD	3,972.000				
25000210	SEEDING CL 2A	ACRE	0.790				
25000400	NITROGEN FERT NUTR	POUND	72.000				
25000500	PHOSPHORUS FERT NUTR	POUND	72.000				
25000600	POTASSIUM FERT NUTR	POUND	72.000				
25100630	EROSION CONTR BLANKET	SQ YD	3,792.000				
25200110	SODDING SALT TOLERANT	SQ YD	160.000				
25200200	SUPPLE WATERING	UNIT	1.000				
28000250	TEMP EROS CONTR SEED	POUND	79.000				
28000400	PERIMETER EROS BAR	FOOT	3,000.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60L98

State Job # - C-91-065-11

Project Number

Route

County Name - COOK - -

NHPP-0344/064/

FAP 344

Code - 31 - -

*REVISED: JUNE 05, 2017

District - 1 - -

Section Number - (524-1&2) RS

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000500	INLET & PIPE PROTECT	EACH	14.000				
28001100	TEMP EROS CONTR BLANK	SQ YD	3,792.000				
28100105	STONE RIPRAP CL A3	SQ YD	810.000				
35501308	HMA BASE CSE 6	SQ YD	77.000				
40600290	BIT MATLS TACK CT	POUND	54,236.000				
40600400	MIX CR JTS FLANGEWYS	TON	254.000				
40600827	P LB MM IL-4.75 N50	TON	3,593.000				
40600982	HMA SURF REM BUTT JT	SQ YD	1,090.000				
40600985	PCC SURF REM BUTT JT	SQ YD	14.000				
40603335	HMA SC "D" N50	TON	9.000				
40603565	P HMA SC "E" N70	TON	8,275.000				
42101300	PROTECTIVE COAT	SQ YD	374.000				
42400200	PC CONC SIDEWALK 5	SQ FT	1,356.000				
42400800	DETECTABLE WARNINGS	SQ FT	40.000				
44000159	HMA SURF REM 2 1/2	SQ YD	72,187.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60L98

State Job # - C-91-065-11

Project Number

Route

County Name - COOK - -

NHPP-0344/064/

FAP 344

Code - 31 - -

*REVISED: JUNE 05, 2017

District - 1 - -

Section Number - (524-1&2) RS

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44000200	DRIVE PAVEMENT REM	SQ YD	77.000				
44000500	COMB CURB GUTTER REM	FOOT	28.000				
44000600	SIDEWALK REM	SQ FT	1,356.000				
44003510	MEDIAN REMOVAL (PD)	SQ FT	10,673.000				
44201717	CL D PATCH T2 6	SQ YD	7.000				
44201753	CL D PATCH T2 9	SQ YD	150.000				
44201757	CL D PATCH T3 9	SQ YD	200.000				
44201759	CL D PATCH T4 9	SQ YD	150.000				
44201839	CL D PATCH T2 16	SQ YD	925.000				
44201843	CL D PATCH T3 16	SQ YD	1,250.000				
44201845	CL D PATCH T4 16	SQ YD	925.000				
44201863	CL D PATCH T2 18	SQ YD	27.000				
44201867	CL D PATCH T3 18	SQ YD	103.000				
44201869	CL D PATCH T4 18	SQ YD	57.000				
48101100	AGGREGATE SHLDS A 12	SQ YD	39.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60L98

State Job # - C-91-065-11

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - (524-1&2) RS

Project Number

NHPP-0344/064/

*REVISED: JUNE 05, 2017

Route

FAP 344

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48102100	AGG WEDGE SHLD TYPE B	TON	538.000				
50104400	CONC HDWL REM	EACH	2.000				
54001001	BOX CUL END SEC C1	EACH	7.000				
54010302	PCBC 3X2	FOOT	133.000				
542A0223	P CUL CL A 1 18	FOOT	386.000				
542A5485	P CUL CL A 1 EQRS 30	FOOT	42.000				
54213663	PRC FLAR END SEC 18	EACH	16.000				
54213675	PRC FLAR END SEC 30	EACH	2.000				
54214515	PRC FL END S EQ RS 30	EACH	2.000				
550A0120	STORM SEW CL A 1 24	FOOT	20.000				
550A0140	STORM SEW CL A 1 30	FOOT	269.000				
55100500	STORM SEWER REM 12	FOOT	89.000				
55100700	STORM SEWER REM 15	FOOT	90.000				
55100900	STORM SEWER REM 18	FOOT	43.000				
55101200	STORM SEWER REM 24	FOOT	290.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60L98

State Job # - C-91-065-11

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - (524-1&2) RS

Project Number

NHPP-0344/064/

*REVISED: JUNE 05, 2017

Route

FAP 344

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60300305	FR & LIDS ADJUST	EACH	2.000				
60402010	GRATES T6	EACH	1.000				
60603800	COMB CC&G TB6.12	FOOT	28.000				
*REV 66900200	NON SPL WASTE DISPOSL	CU YD	253.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
*REV 66900530	SOIL DISPOSAL ANALY	EACH	3.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100600	TRAF CONT-PROT 701336	L SUM	1.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				
70102622	TR CONT & PROT 701502	L SUM	1.000				
70102625	TR CONT & PROT 701606	L SUM	1.000				
70102630	TR CONT & PROT 701601	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

60L98

State Job # - C-91-065-11

County Name - COOK- -

Code - 31 - -

District - 1 - -

Section Number - (524-1&2) RS

Project Number

NHPP-0344/064/

*REVISED: JUNE 05, 2017

Route

FAP 344

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70102635	TR CONT & PROT 701701	L SUM	1.000				
70102640	TR CONT & PROT 701801	L SUM	1.000				
70300100	SHORT TERM PAVT MKING	FOOT	11,866.000				
70300150	SHRT TRM PAVT MK REM	SQ FT	3,956.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	947.000				
70300220	TEMP PVT MK LINE 4	FOOT	77,163.000				
70300240	TEMP PVT MK LINE 6	FOOT	4,089.000				
70300260	TEMP PVT MK LINE 12	FOOT	1,657.000				
70300280	TEMP PVT MK LINE 24	FOOT	564.000				
70300520	PAVT MARK TAPE T3 4	FOOT	5,933.000				
72400500	RELOC SIN PAN ASSY TA	EACH	1.000				
72800100	TELES STL SIN SUPPORT	FOOT	8.000				
78000100	THPL PVT MK LTR & SYM	SQ FT	947.000				
78000200	THPL PVT MK LINE 4	FOOT	77,163.000				
78000400	THPL PVT MK LINE 6	FOOT	4,089.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60L98

State Job # - C-91-065-11

County Name - COOK - -

Code - 31 - -

District - 1 - -

Section Number - (524-1&2) RS

Project Number

NHPP-0344/064/

*REVISED: JUNE 05, 2017

Route

FAP 344

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78000600	THPL PVT MK LINE 12	FOOT	1,657.000				
78000650	THPL PVT MK LINE 24	FOOT	564.000				
78100100	RAISED REFL PAVT MKR	EACH	825.000				
78300200	RAISED REF PVT MK REM	EACH	660.000				
85000200	MAIN EX TR SIG INSTAL	EACH	3.000				
88600600	DET LOOP REPL	FOOT	1,881.000				
89500400	RELOC EX PED PUSH-BUT	EACH	1.000				
89502376	REBUILD EX HANDHOLE	EACH	6.000				
89502378	REBLD EX HH TO HD HH	EACH	6.000				

CONTRACT NUMBER

60L98

THIS IS THE TOTAL BID

\$ _____

NOTES:

- 1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.**
- 2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.**
- 3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.**
- 4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.**

BUTT JOINTS (BDE)	51
COMPENSABLE DELAY COSTS (BDE).....	52
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE)	56
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE).....	58
QUALITY CONTROL FOR PERFORMANCE (BDE).....	70
HOT-MIX ASPHALT – TACK COAT (BDE)	75
PROGRESS PAYMENTS (BDE)	75
TEMPORARY PAVEMENT MARKING (BDE).....	76
TRAINING SPECIAL PROVISIONS (BDE)	79
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION ..	81
WARM MIX ASPHALT (BDE)	84
WEEKLY DBE TRUCKING REPORTS (BDE).....	86
WORKING DAYS (BDE).....	86
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID).....	86
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID).....	89
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES.....	93

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

This work shall be according to Article 669 of the Standard Specifications and the following:

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This **Revised Special Provision** will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as either “uncontaminated soil” or non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances. The Environmental Firm shall continuously monitor all soil excavation for worker protection and soil contamination. **Phase I Preliminary Engineering information is available through the District’s Environmental Studies Unit.** Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

The Contractor shall manage any excavated soils and sediment within the following areas:

Intersection of IL Route 83 and S. 76th Avenue

- All excavation planned at the southwest quadrant at the intersection of Illinois Route 83 and S. 76th Avenue, Palos Heights. This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL Route 83 and Princeton Lane (west intersection)

- All excavation planned at the southwest quadrant, center median, and southeast quadrant at the intersection of IL Route 83 and Princeton Lane (west intersection), Palos Heights. This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

Intersection of IL Route 83 and Princeton Lane (east intersection)

- All excavation planned at the center median at the intersection of IL Route 83 and Princeton Lane (east intersection), Palos Heights. This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Potential contaminants of concern sampling parameters: VOCs, SVOCs and Metals.

IL Route 83 (Cal-Sag Road) from 71st Avenue to 68th Avenue

- Station 188+00 to Station 206+00 (CL IL Route 83 [Cal-Sag Road]), 0 to 50 feet RT and 0 to 50 feet LT, Palos Heights, for drainage and grading improvements. This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: VOCs, SVOCs, Metals.