

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	90% FEDERAL 10% STATE ROADWAY	90% FEDERAL 10% STATE ROADWAY
				0005 URBAN	0005 URBAN	0021 URBAN	0021 RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	312			81	231
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	56920	15138	41782		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24	6	18		
40600535	LEVELING BINDER (HAND METHOD), N70	TON	41	11	30		
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG,N70	TON	3428	885	2543		
40600990	TEMPORARY RAMP	SQ YD	1130	536	594		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7086	1830	5256		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	226	141	85		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2683	1673	1010		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	81627	21072	60555		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	13870			3585	10285
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	31207			8066	23141
△ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	35	35			
△ 66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	0.25	0.75		

△ SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISOR	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				840	(14)RS-5	KANKAKEE	14	3
DESIGNED	CHECKED	DATE	REVISOR	SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	[ILLINOIS] FED. AID PROJECT		
...	CONTRACT NO. 66A98		

6-5-17, RW