

SAFETY SHOULDER AND RUMBLE STRIP SCHEDULE					
LOCATION	LENGTH	CL RUMBLE 16"	HMA SHOULDER 8"	EXCAVATING & GRADING EXISTING SHOULDER	RUMBLE STRIPS 8"
STA	FOOT	FOOT	SQ YD	UNIT	FOOT
484+50 - 525+35	4085	3444	3585	81	8066
URBAN TOTAL	4085	3444	3585	81	8066
525+35 - 566+60	4125	3350	3542	80	7970
566+60 - 582+93	1633	1633	1391	31	3130
582+93 - 643+60	6067	6067	5352	120	12041
RURAL TOTAL	11825	11050	10285	231	23141
PROJECT TOTAL	15910	14494	13870	312	31207

SIDE ROAD AND ENTRANCE SCHEDULE						
LOCATION	DESCRIPTION	SURFACE	HMA SURF REM 1-1/2"	TEMP RAMP	BIT MATLS (TACK CT)	INC HMA SURF
STA			SQ YD	SQ YD	LBS	TON
485+30 LT	CE	HMA/AGG	33		15	2.8
485+70 RT	CE	HMA	84	22	38	7.1
485+90 LT	CE	HMA	49	14	22	4.1
486+80 LT	CE	HMA	41	16	18	3.4
487+50 LT	PE	HMA	63		28	5.3
488+30 RT	PE	HMA	44		20	3.7
525+33 RT	10000 N RD	HMA	1359	24	612	114.2
URBAN TOTAL			1673	76	753	140.6
525+37 LT	10000 N RD	HMA	130	14	59	10.9
554+68 RT	CE	HMA/AGG	43		19	3.6
556+70 RT	CE	HMA	40	11	18	3.4
558+30 RT	CE	HMA	50	13	23	4.2
559+50 RT	CE	HMA	41	16	18	3.4
560+10 RT	CE	HMA	45	13	20	3.8
561+50 RT	CE	AGG	126	16	57	10.6
566+60 RT	3000 E RD	HMA	243	22	109	20.4
582+93 RT	11000 N RD	HMA	150	17	68	12.6
582+93 LT	11000 N RD	HMA	142	12	64	11.9
RURAL TOTAL			1010	134	455	84.8
PROJECT TOTAL			2683	210	1208	225.4

FILE NAME :	USER NAME :	DESIGNED :	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE. :	SECTION :	COUNTY :	TOTAL SHEETS :	SHEET NO. :	
pw\N\084EBID\INTEG\Illinois.gov\PW\DOT\Documents\DOT Offices\District 3\Projects\0364\DRAW\0364\08-shr-details.DGN		CHECKED :	REVISED :			840	(14)RS-5	KANKAKEE	13	8	
Default		DATE :	REVISED :			SCALE:	SHEET OF SHEETS	STA. TO STA.	CONTRACT NO. 66A98		
									ILLINOIS FED. AID PROJECT		

A REV 6-5-17BM