

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	90% FEDERAL 10% STATE ROADWAY	90% FEDERAL 10% STATE ROADWAY
				0005 URBAN	0005 URBAN	0021 URBAN	0021 RURAL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	312			81	231
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	56920	15138	41782		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	24	6	18		
40600535	LEVELING BINDER (HAND METHOD), N70	TON	41	11	30		
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5FG,N70	TON	3428	885	2543		
40600990	TEMPORARY RAMP	SQ YD	1130	536	594		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7086	1830	5256		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	226	141	85		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	2683	1673	1010		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	81627	21072	60555		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	13870			3585	10285
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	31207			8066	23141
△ 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	35	35			
△ 66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	0.25	0.75		

△ SPECIALTY ITEMS

FILE NAME	USER NAME	DESIGNED	REVISOR	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...	...	...	...	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				840	(14)RS-5	KANKAKEE	14	3
DESIGNED	CHECKED	DATE	REVISOR	SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	[ILLINOIS] FED. AID PROJECT		
...	...	...	...							CONTRACT NO. 66A98		

6-5-17, RW

SAFETY SHOULDER AND RUMBLE STRIP SCHEDULE					
LOCATION	LENGTH	CL RUMBLE 16"	HMA SHOULDER 8"	EXCAVATING & GRADING EXISTING SHOULDER	RUMBLE STRIPS 8"
STA	FOOT	FOOT	SQ YD	UNIT	FOOT
484+50 - 525+35	4085	3444	3585	81	8066
<b>URBAN TOTAL</b>	<b>4085</b>	<b>3444</b>	<b>3585</b>	<b>81</b>	<b>8066</b>
525+35 - 566+60	4125	3350	3542	80	7970
566+60 - 582+93	1633	1633	1391	31	3130
582+93 - 643+60	6067	6067	5352	120	12041
<b>RURAL TOTAL</b>	<b>11825</b>	<b>11050</b>	<b>10285</b>	<b>231</b>	<b>23141</b>
<b>PROJECT TOTAL</b>	<b>15910</b>	<b>14494</b>	<b>13870</b>	<b>312</b>	<b>31207</b>

SIDE ROAD AND ENTRANCE SCHEDULE						
LOCATION	DESCRIPTION	SURFACE	HMA SURF REM 1-1/2"	TEMP RAMP	BIT MATLS (TACK CT)	INC HMA SURF
STA			SQ YD	SQ YD	LBS	TON
485+30 LT	CE	HMA/AGG	33		15	2.8
485+70 RT	CE	HMA	84	22	38	7.1
485+90 LT	CE	HMA	49	14	22	4.1
486+80 LT	CE	HMA	41	16	18	3.4
487+50 LT	PE	HMA	63		28	5.3
488+30 RT	PE	HMA	44		20	3.7
525+33 RT	10000 N RD	HMA	1359	24	612	114.2
<b>URBAN TOTAL</b>			<b>1673</b>	<b>76</b>	<b>753</b>	<b>140.6</b>
525+37 LT	10000 N RD	HMA	130	14	59	10.9
554+68 RT	CE	HMA/AGG	43		19	3.6
556+70 RT	CE	HMA	40	11	18	3.4
558+30 RT	CE	HMA	50	13	23	4.2
559+50 RT	CE	HMA	41	16	18	3.4
560+10 RT	CE	HMA	45	13	20	3.8
561+50 RT	CE	AGG	126	16	57	10.6
566+60 RT	3000 E RD	HMA	243	22	109	20.4
582+93 RT	11000 N RD	HMA	150	17	68	12.6
582+93 LT	11000 N RD	HMA	142	12	64	11.9
<b>RURAL TOTAL</b>			<b>1010</b>	<b>134</b>	<b>455</b>	<b>84.8</b>
<b>PROJECT TOTAL</b>			<b>2683</b>	<b>210</b>	<b>1208</b>	<b>225.4</b>

FILE NAME : p:\N\084EBID\INTEG\Illinois.gov\PW\DOT\Documents\DOT Offices\District 3\Projects\0364\DRAW\0364\08-shr-details.DGN	USER NAME : cbrccorinm	DESIGNED - -	REVISED - -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>			F.A.P. RTE. 840	SECTION (14)RS-5	COUNTY KANKAKEE	TOTAL SHEETS 13	SHEET NO. 8
Default	PLOT SCALE : 100,0000 ' / in.	CHECKED - -	REVISED - -					SCALE:	SHEET	OF	SHEETS	STA.
	PLOT DATE : 5/31/2017	DATE - -	REVISED - -									

A REV 6-5-17BM