

URBAN

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		COOK COUNTY 0014	LAKE COUNTY 0014			
50200100	STRUCTURE EXCAVATION	CU YD	60	60				
20400800	FURNISHED EXCAVATION	CU YD	7	7				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	70	70				
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9				
25100630	EROSION CONTROL BLANKET	SO YD	70	70				
28000400	PERIMETER EROSION BARRIER	FOOT	55	55				
50102400	CONCRETE REMOVAL	CU YD	7.7	7.7				
50300225	CONCRETE STRUCTURES	CU YD	5.9	5.9				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.75	0.875	0.875			
50300300	PROTECTIVE COAT	SO YD	23	23				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	820	820				
52200020	TEMPORARY SOIL RETENTION SYSTEM	SO FT	355	355				
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	123	123				
* 63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	37.5	37.5				

SUMMARY OF QUANTITIES				TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	100% State COOK COUNTY 0014		100% State LAKE COUNTY 0014	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
63200310	GUARDRAIL REMOVAL	FOOT	261	261		
66900200	NON SPECIAL WASTE DISPOSAL	CU YD	50	50		▲
64300750	IMPACT ATTENUATORS (SEVERE USE, NARROW), TEST LEVEL 2	EACH	2	2		
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1		▲
67100100	MOBILIZATION	LSUM	1	1		
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1		▲
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	3200	3200		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1800	1800		
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SO FT	600	600		
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	10.4	10.4		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	1		
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SO FT	1070	1070		
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	102.8	102.8		

FILE NAME :	USER NAME = mkg/jd	DESIGNED -	REVISED -
OFFICIALS/DESIGNER/PROJECT/DATE/SCALE/PLLOT DATE	OFFICIALS/DESIGNER/PROJECT/DATE/SCALE/PLLOT DATE	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
LAKE COOK ROAD OVER CREEK 0.6 MILES WEST OF ELA ROAD**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1270	0707-CLV	COOK	11	3
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 62094				

▲ REV 6-7-17 REV