



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2023

SUBJECT: TR 209A (Windsor Road)
Section 22-03122-00-BR
Champaign County
Contract No. 91632
Item 098
June 16, 2023 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Plan Sheet 6**
- 2. Revised Special Provision Index**
- 3. Added page 7A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

SPECIAL PROVISIONS TABLE OF CONTENTS

CONTRACT SPECIFICATIONS1
DESCRIPTION OF WORK1
PREQUALIFICATION OF BIDDERS1
PREVAILING WAGE1
PROJECT MAINTENANCE2
CONTRACTOR AVAILABILITY2
STANDARDS IN THE PLANS2
CONTRACTOR RESPONSIBILITY2
UTILITIES2
STATUS OF UTILITIES3
PROTECTION AND RESTORATION OF TRAFFIC SIGNS4
REMOVAL OF EXISTING SUPERSTRUCTURES4
REMOVAL OF UNCLASSIFIED MATERIALS4
MEASUREMENTS OF GRANULAR MATERIALS5
TRAFFIC CONTROL PLAN5
RIGHT-OF-WAY6
SEEDING, CLASS 2 (SPECIAL)6
PIPE DRAINS AND HEADWALLS7
EXISTING FIELD TILE REMOVAL7
PRECAST CONCRETE DECKING PROTECTIVE COAT (SPECIAL)7
PIPE DRAINS AND HEADWALLS 7A
EXISTING FIELD TILE REMOVAL 7A
NATIONWIDE NO. 14 PERMIT9
LR 107-4 12
LR 702 13

PIPE DRAINS AND HEADWALLS

This work shall be performed in accordance with Section 611 of the Standard Specifications, the provisions herein and as directed by the Engineer. Pipe drains of the correct size and concrete headwalls shall be used at locations deemed necessary by the Engineer.

The headwalls shall be constructed according to the Highway Standard 601101 with the exception that it shall be modified to match the proposed grade and pipe size for each field tile location shown in the plans. Shop drawings shall be provided to the Engineer for approval prior to ordering precast headwalls. This work shall be completed to the satisfaction of the Engineer.

This work shall be paid for at the contract unit price per EACH for CONCRETE HEAD WALLS FOR PIPE DRAINS or FOOT for PIPE DRAINS of the correct size, which price shall include all labor, equipment and materials necessary to complete the work.

EXISTING FIELD TILE REMOVAL

This work consists of the removal and satisfactory disposal of existing field tiles in accordance with the applicable portions of Section 501 and 611 of the Standard Specifications and as directed by the Engineer.

This work will be paid for at the contract unit price per FOOT for EXISTING FIELD TILE REMOVAL, which price shall include all labor, equipment and materials necessary to complete the work.