



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 2, 2023

SUBJECT: TR 201A (Kirby Avenue)  
Section 22-03123-00-BR  
Champaign County  
Contract No. 91633  
Item 099  
June 16, 2023 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Plan Sheet 6**
- 2. Revised Special Provision Index**
- 3. Added page 7A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

**SPECIAL PROVISIONS TABLE OF CONTENTS**

CONTRACT SPECIFICATIONS .....	1
DESCRIPTION OF WORK .....	1
PREQUALIFICATION OF BIDDERS .....	1
PREVAILING WAGE .....	1
PROJECT MAINTENANCE .....	2
CONTRACTOR AVAILABILITY .....	2
STANDARDS IN THE PLANS .....	2
CONTRACTOR RESPONSIBILITY .....	2
UTILITIES .....	2
STATUS OF UTILITIES .....	3
PROTECTION AND RESTORATION OF TRAFFIC SIGNS .....	3
REMOVAL OF EXISTING SUPERSTRUCTURES .....	4
REMOVAL OF UNCLASSIFIED MATERIALS .....	4
MEASUREMENTS OF GRANULAR MATERIALS .....	4
TRAFFIC CONTROL PLAN .....	5
RIGHT-OF-WAY .....	6
SEEDING, CLASS 2 (SPECIAL) .....	6
PIPE DRAINS AND HEADWALLS .....	7
EXISTING FIELD TILE REMOVAL .....	7
PRECAST CONCRETE DECKING PROTECTIVE COAT (SPECIAL) .....	7
PIPE DRAINS AND HEADWALLS .....	7A
EXISTING FIELD TILE REMOVAL .....	7A
NATIONWIDE NO. 14 PERMIT .....	9
LR 107-4 .....	12
LR 702 .....	13

### **PIPE DRAINS AND HEADWALLS**

This work shall be performed in accordance with Section 611 of the Standard Specifications, the provisions herein and as directed by the Engineer. Pipe drains of the correct size and concrete headwalls shall be used at locations deemed necessary by the Engineer.

The headwalls shall be constructed according to the Highway Standard 601101 with the exception that it shall be modified to match the proposed grade and pipe size for each field tile location shown in the plans. Shop drawings shall be provided to the Engineer for approval prior to ordering precast headwalls. This work shall be completed to the satisfaction of the Engineer.

This work shall be paid for at the contract unit price per EACH for CONCRETE HEAD WALLS FOR PIPE DRAINS or FOOT for PIPE DRAINS of the correct size, which price shall include all labor, equipment and materials necessary to complete the work.

### **EXISTING FIELD TILE REMOVAL**

This work consists of the removal and satisfactory disposal of existing field tiles in accordance with the applicable portions of Section 501 and 611 of the Standard Specifications and as directed by the Engineer.

This work will be paid for at the contract unit price per FOOT for EXISTING FIELD TILE REMOVAL, which price shall include all labor, equipment and materials necessary to complete the work.