F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20R-5	LAKE	562	308
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
D-91-552-99				60881

IL ROUTE 22 (HALF DAY ROAD) - SCHEDULE OF SIGNS

APPROX. STATION	SIGN PANEL TYPE	WIDTH mm	HEIGHT mm	AREA mm²	POST TYPE	QUANTITY	LENGTH m	CONCRETE FOUNDATIONS ea	REMARKS
102+395 LT	A	600	450	0.270	ON SAME POST AS ABOVE				W11-8P
102+419 LT	B	750	900	0.675	A	2	4.1		R3-5L
102+419 LT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
102+436 RT	B	750	750	0.563	B	2	4.5		R3-2
102+436 RT	B	969	450	0.436	ON SAME POST AS ABOVE				6AM - 9AM MON-FRI
102+439 LT	1	750	750	0.563	B	1	4.05		R1-1
102+440 LT									RELOCATE "EASTON AVE"
									AND POST
102+460 LT	1	600	750	0.450	B	1	4.05		R4-7
102+461 RT									RELOCATE "EASTON AVE"
									AND POST
102+463 LT	B	750	750	0.563	B	2	4.5		R3-2
102+463 LT	B	969	450	0.436	ON SAME POST AS ABOVE				BLACK ON WHITE-
									6AM - 9AM MON-FRI
102+554 LT	B	1200	450	0.540	WOOD	1	4.8	1	VILLAGE NAME WHITE ON GREEN-
									BUFFALO GROVE 43000
102+554 LT	B	600	750	0.450	ON SAME POST AS ABOVE				R2-1 (45MPH)
102+555 RT	B	1350	450	0.608	WOOD	2	4.8	2	WHITE ON GREEN -
									PRAIRIE VIEW UNINCORPORATED
102+555 RT	B	600	750	0.450	ON SAME POST AS ABOVE				R2-1 (35MPH)
102+648 LT	B	750	900	0.675	A	2	4.10		R3-5L
102+648 LT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
102+671 LT									RELOCATE "FIORE NURSERY"
									AND POSTS
102+698 LT	1	600	750	0.450	B	1	4.05		R4-7
102+747 RT					B	1	4.05		RELOCATE METRA AND ARROW
102+800 RT	1	900	900	0.810	A	2	4.1		W10-1
102+814 LT	B	750	900	0.675	A	2	4.10		R3-5L
102+814 LT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
102+868 LT									RELOCATE EXISTING "PRAIRIE
									VIEW SIGNS" BY OTHERS
102+887 LT					B	1	4.35		RELOCATE "VERNON
									TOWNSHIP CENTER"
102+888 RT	B	750	900	0.675	A	2	4.10		R3-5L
102+888 RT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
102+889 LT					B	1	4.35		RELOCATE METRA AND ARROW
102+906 RT	1	600	750	0.450	B	1	4.05		R8-8
102+929 LT	1	600	750	0.450	B	1	4.05		R8-8
102+929 LT	1	900	900	0.810	ON SAME POST AS ABOVE				CAUTION (BLACK ON YELLOW)
102+929 LT	1	900	900	0.810	ON SAME POST AS ABOVE				125 FT BETWEEN TRACKS AND
									HIGHWAY (BLACK ON WHITE)
102+940 LT	1	1050	300	0.315	WOOD	1	3.9	1	STREET NAME - WHITE ON GREEN
									PRAIRIE RD
102+943 RT	1	750	750	0.563	B	1	4.05		R3-2

IL ROUTE 22 (HALF DAY ROAD) - SCHEDULE OF SIGNS

APPROX. STATION	SIGN PANEL TYPE	WIDTH mm	HEIGHT mm	AREA mm²	POST TYPE	QUANTITY	LENGTH m	CONCRETE FOUNDATIONS ea	REMARKS
102+945 LT	1	750	750	0.563	B	1	4.05	1	R1-1
102+960 LT									RELOCATE "ODD EVEN SPRINKLING
									RESTRICTIONS WATERING
									PROHIBITED NOON TO 6PM
									MAY 15-SEPT 15" AND POST
102+973 RT	1	750	750	0.563	B	1	4.05		R3-2
103+029 LT	1	900	900	0.810	A	2	4.1		W10-1
103+096 RT									RELOCATE "PRIVATE PARKING
									UNAUTHORIZED CARS WILL BE
									TOWED AWAY" AND POST
103+105 LT	B	900	900	0.810	B	2	4.5		W3-3
103+105 LT	B	900	300	0.270	ON SAME POST AS ABOVE				BLACK ON YELLOW-PRAIRIE RD
103+134									RELOCATE R2-1(35MPH) AND POST
103+161									RELOCATE R2-1(35MPH) AND POST
103+196 RT									RELOCATE "PRIVATE PARKING
									UNAUTHORIZED CARS WILL BE
									TOWED AWAY" AND POST
103+184 LT	B	750	900	0.675	A	2	4.10		R3-5L
103+184 LT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
103+218 RT									RELOCATE PRIVATE STOP SIGN
									AND POST
103+206 LT	1	750	750	0.563	B	1	4.05		R1-1
103+208 LT	1	750	900	0.675	A	2	4.05		R3-5R
103+224 LT	1	750	300	0.225	A	1	3.5		STREET NAME - WHITE ON GREEN
									PRAIRIE LN
103+241 RT	B	600	750	0.450	B	1	4.05		R4-7
103+241 RT	B	750	900	0.675	ON SAME POST AS ABOVE				R3-5L
103+254 RT									RELOCATE PRIVATE STOP SIGN
									AND POST
103+322 LT	B	750	900	0.675	A	2	4.10		R3-5L
103+322 LT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
103+348 LT	1	750	750	0.563	B	1	4.05		R1-1
103+366 RT	1	750	750	0.563	B	1	4.05		R1-1
103+367 LT	1	900	300	0.270	B	1	3.6		STREET NAME - WHITE ON GREEN
									APPLE HILL LN
103+364 LT	1	600	750	0.450	B	1	4.05		R2-1(30MPH)
103+379 RT									RELOCATE "APPLE HILL LN"
									AND POST
103+388 RT	B	750	900	0.675	A	2	4.10		R3-5L
103+388 RT	B	600	750	0.450	ON SAME POST AS ABOVE				R4-7
103+396 RT									RELOCATE "STEVENSON HIGH
									SCHOOL" AND POST
103+438 LT	B	1350	450	0.608	WOOD	2	4.05	2	WHITE ON GREEN -
									PRAIRIE VIEW UNINCORPORATED

NOTES:

1. SEE TRAFFIC SIGNAL PLANS FOR MAST ARM MOUNTED STREET NAME SIGN QUANTITIES.
2. REGULATORY SIGNS SHALL BE IN ACCORDANCE WITH THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES.
3. APPROXIMATE STATIONS ARE GIVEN FOR SIGN LOCATIONS. FINAL LOCATION OF SIGNS WILL BE DETERMINED IN THE FIELD SUBJECT TO THE ENGINEERS APPROVAL.
4. ALL SIGNS TO BE OFFSET 0.6M FROM FACE OF CURB, EXCEPT AT AREAS WITH GUARDRAIL. AT THOSE LOCATIONS SIGNS SHALL BE PLACED BEHIND THE GUARDRAIL.
5. THE ACTUAL SPEED LIMITS SHOWN ON NEW OR RELOCATED SPEED LIMIT SIGNS SHALL BE VERIFIED WITH IDOT BUREAU OF TRAFFIC PRIOR TO INSTALLATION OR RELOCATION.

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK		
NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK		
NO.		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
IL RTE 22 (FAP 337)
IL RTE 83 TO US 45 / IL 21 (MILWAUKEE AVE)

PROPOSED SIGNING SCHEDULE
SHEET 2 OF 4

SCALE: NONE DRAWN BY: AMB
DATE: 03-22-2004 CHECKED BY: JNR

p:\00332\Road\22proesignsc2.dgn 04/15/2004 03:52:49 PM