

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20 WRS-6	LAKE	318	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62030				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNAL RTE 22 @ OAKWOOD/OLD MILL GROVE	TRAFFIC SIGNAL RTE 22 @ OQUENTIN	TRAFFIC SIGNAL INTERCONNECT	TRAFFIC SIGNAL EMERGENCY PRE-EMPTION	LAKE ZURICH		
				80% FED 20% STATE J000-2A	80% FED 10% STATE 10% LAKE ZURICH Y031-1F	80% FED 10% STATE 10% LAKE Co. Y031-1F	80% FED 20% STATE Y031-1F	100% LAKE ZURICH Y031-3D	100% LAKE ZURICH Y060		
M2520200	SUPPLEMENTAL WATERING	UNIT	458	458							
M2800250	TEMPORARY EROSION CONTROL SEEDING	KG	626	626.0							
M2800400	PERIMETER EROSION BARRIER	METER	3,498	3,498							
M2810705	STONE DUMPED RIPRAP, CLASS A3	SQ M	64	64							
M2810107	STONE DUMPED RIPRAP, CLASS A4	SQ M	56	56							
M2820100	FILTER FABRIC	SQ M	120	120							
M4021010	AGGREGATE SURFACE COURSE, TYPE B	M TON	1,109	1,109							
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	11	11							
M4060300	AGGREGATE PRIME COAT	M TON	24	24							
M4060895	CONSTRUCTING TEST STRIP	EACH	2	2							
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	55,067	55,067							
M4205200	PROTECTIVE COAT	SQ M	65,387	65,387							
M4240125	PORTLAND CEMENT CONCRETE SIDEWALK, 125MM	SQ M	84	84							
M4402000	PAVEMENT REMOVAL	SQ M	40,740	40,740							
M4402010	DRIVEWAY PAVEMENT REMOVAL	SQ M	2,601	2,601.0							
M4402020	CURB REMOVAL	METER	221	221							
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	2,424	2,424							
M4402050	SIDEWALK REMOVAL	SQ M	119	119							
M4428040	CLASS D PATCHES, TYPE I, 300MM	SQ M	94	94							
M4428240	CLASS D PATCHES, TYPE II, 300MM	SQ M	576	576							
M4428340	CLASS D PATCHES, TYPE III, 300MM	SQ M	621	621							
M4428440	CLASS D PATCHES, TYPE IV, 300MM	SQ M	449	449							
M4812200	AGGREGATE SHOULDERS, TYPE B 200MM	SQ M	1,195	1,195							
M4812250	AGGREGATE SHOULDERS, TYPE B 250MM	SQ M	4,945	4,945							
M5010522	PIPE CULVERT REMOVAL	METER	67	67							
M5080105	REINFORCEMENT BARS	KG	4,885	4,885							
M5120900	TEMPORARY SHEET PILING	SQ M	141	141							

⊙ - DENOTES SPECIALTY ITEMS
 △ - Y080 COST CODE

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22
NAME	DATE	
		SUMMARY OF QUANTITIES
SCALE NTS		DRAWN BY: SMP
DATE: 03/11/05		CHECKED BY: BDH