

| | | | | |
|---------------------|----------|----------|------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 337 | 20 WRS-6 | LAKE | 318 | 8 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS | FED. AID PROJECT | |
| CONTRACT NO. 62030 | | | | |

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | URBAN TOTAL QUANTITY | ROADWAY | TRAFFIC SIGNAL RTE 22 @ OAKWOOD/OLD MILL GROVE | TRAFFIC SIGNAL RTE 22 @ QUENTIN | TRAFFIC SIGNAL INTERCONNECT | TRAFFIC SIGNAL EMERGENCY PRE-EMPTION | LAKE ZURICH | | |
|----------|---|-------|----------------------|---------------------------|--|--|-----------------------------|--------------------------------------|-----------------------|-------|--|
| | | | | 80% FED 20% STATE J000-2A | 80% FED 10% STATE 10% LAKE ZURICH Y031-1F | 80% FED 10% STATE 10% LAKE CO. Y031-1F | 80% FED 20% STATE Y031-1F | 100% LAKE ZURICH Y031-3D | 100% LAKE ZURICH Y060 | | |
| M5502890 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 675MM | METER | 68.0 | 68.0 | | | | | | | |
| M5502900 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 750MM | METER | 26.5 | 26.5 | | | | | | | |
| M5503050 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 300MM | METER | 1,310.3 | 1,310.3 | | | | | | | |
| M5503060 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 375MM | METER | 275.3 | 275.3 | | | | | | | |
| M5503070 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 450MM | METER | 452.3 | 452.3 | | | | | | | |
| M5503080 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 525MM | METER | 156.9 | 156.9 | | | | | | | |
| M5503090 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 600MM | METER | 526.3 | 526.3 | | | | | | | |
| M5503100 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 675MM | METER | 204.4 | 204.4 | | | | | | | |
| M5503111 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 750MM | METER | 34.7 | 34.7 | | | | | | | |
| M5503300 | STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 600MM | METER | 172.8 | 172.8 | | | | | | | |
| M5503340 | STORM SEWERS, TYPE 3, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 900MM | METER | 15.0 | 15.0 | | | | | | | |
| M5504410 | STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 750MM, RISE 475MM | METER | 32.5 | 32.5 | | | | | | | |
| M5504550 | STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 1125MM, RISE 725MM | METER | 33.5 | 33.5 | | | | | | | |
| M5505540 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 375MM | METER | 47.1 | 47.1 | | | | | | | |
| M5505930 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 300MM | METER | 50.1 | 50.1 | | | | | | | |
| M5505940 | STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 375MM | METER | 50.1 | 50.1 | | | | | | | |
| M5510015 | STORM SEWER REMOVAL 200MM | METER | 7 | 7 | | | | | | | |
| M5510025 | STORM SEWER REMOVAL 300MM | METER | 280 | 280 | | | | | | | |
| M5510035 | STORM SEWER REMOVAL 375MM | METER | 161 | 161 | | | | | | | |
| M5510045 | STORM SEWER REMOVAL 450MM | METER | 337 | 337 | | | | | | | |
| M5510060 | STORM SEWER REMOVAL 600MM | METER | 299 | 299 | | | | | | | |
| M5610415 | DUCTILE IRON WATER MAIN 150MM | METER | 51.6 | | | | | | | 51.6 | |
| M5610420 | DUCTILE IRON WATER MAIN 200MM | METER | 3.0 | | | | | | | 3.0 | |
| M5610430 | DUCTILE IRON WATER MAIN 300MM | METER | 642.0 | | | | | | | 642.0 | |
| M5610635 | WATER VALVES 150MM | EACH | 3 | | | | | | | 3 | |
| M5610650 | WATER VALVES 300MM | EACH | 5 | | | | | | | 5 | |
| M5620115 | WATER SERVICE LINE, 25MM | METER | 42.0 | | | | | | | 42.0 | |
| M6010605 | PIPE UNDERDRAINS 100MM | METER | 872.6 | 872.6 | | | | | | | |

⊙ - DENOTES SPECIALTY ITEMS
 △ - Y080 COST CODE

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22 |
|----------------|------|--|
| NAME | DATE | |
| | | SUMMARY OF QUANTITIES |
| | | |
| | | |
| | | |
| | | |
| SCALE NTS | | DRAWN BY: SMP |
| DATE: 03/11/05 | | CHECKED BY: BDH |