

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
337	20 WRS-6	LAKE	318	13
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62030				

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNAL RTE 22 @ OAKWOOD/OLD MILL GROVE	TRAFFIC SIGNAL RTE 22 @ QUENTIN	TRAFFIC SIGNAL INTERCONNECT	TRAFFIC SIGNAL EMERGENCY PRE-EMPTION	LAKE ZURICH
				80% FED 20% STATE J000-2A	80% FED 10% STATE 10% LAKE ZURICH Y031-1F	80% FED 10% STATE 10% LAKE CO. Y031-1F	80% FED 20% STATE Y031-1F	100% LAKE ZURICH Y031-3D	100% LAKE ZURICH Y060
X0323116	REFLECTOR MARKERS, TYPE B	EACH	4	4					
X0323260	SEDIMENT BASIN	EACH	3	3					
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	18	18					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	16	16					
X4023000	TEMPORARY ACCESS (ROAD)	EACH	8	8					
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	64	64					
X8050015	SERVICE INSTALLATION - POLE MOUNT	EACH	2		1	1			
X8800020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	8		4	4			
X8800040	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4				
X8800045	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10		4	6			
X8800070	SIGNAL HEAD, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2			2			
X8805280	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	2			2			
X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	2		2				
X0324971	INLETS, 1.2M DIAMETER, SPECIAL	EACH	1	1					
MX407515	BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH), SUPERPAVE, 365MM	SQ M	10,209	10,209					
MX090315	DROP SANITARY MANHOLES, 1.2M DIAMETER WITH FRAME, LID AND CHIMNEY SEAL	EACH	1					1	
**Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	14	14					
**Z0030360	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	7	7					
MX033540	PIPE CULVERT REMOVAL, 300MM	METER	153	153					
M7802000	POLYUREA PAVEMENT MARKING, TYPE I - LETTERS AND SYMBOLS	SQ M	103	103					
MX033541	SALVAGE, STORE AND REINSTALL CABINET, MODEM AND SOLAR PANEL	EACH	1				1		
MX030551	SANITARY SEWER, DUCTILE IRON PIPE, 200MM DIAMETER, AUGERED	METER	28.2						28.2
MX560012	SANITARY SEWER, DUCTILE IRON PIPE, 250MM DIAMETER	METER	57.0						57.0
X0324970	SANITARY SEWER PIPE PROTECTION	EACH	8						8
M3067900	STEEL CASING 550MM	METER	47.0						47.0
MX030572	STEEL CASING AUGERED AND JACKED 550MM	METER	40.2						40.2

** - SFTY-3N
 ● - DENOTES SPECIALTY ITEMS
 △ - Y080 COST CODE

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION ILLINOIS ROUTE 22
NAME	DATE	
		SUMMARY OF QUANTITIES

SCALE NTS DRAWN BY: SMP
 DATE: 03/11/05 CHECKED BY: BDH

Rev.

C:\p001\11111\12141414\03/11/05