

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3545	54-WRS-7	DUPAGE	235	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62291				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS RTE 56 @ SUMMIT/MIDWEST RD	SUMMIT/MIDWEST PRE-EMPTION EQUIPMENT	TRAFFIC SIGNALS RTE 56 @ MYRTLE/MACARTHUR	MYRTLE/MACARTHUR PRE-EMPTION EQUIPMENT	TRAFFIC SIGNAL INTERCONNECT	SIDEWALK	BIKE PATH	OAK BROOK WATER MAIN	OAKBROOK TERRACE WATER MAIN	OAK BROOK SEWER UPGRADE	OAKBROOK TERRACE SEWER UPGRADE	HINSDALE SANITARY DISTRICT SEWER	
				100% STATE	90% STATE 10% DUPAGE	100% OAKBROOK TERRACE	90% STATE 10% OAKBROOK	100% OAKBROOK TERRACE	100% STATE	50% STATE 50% OAKBROOK	100% OAKBROOK TERRACE	75% STATE 25% OAKBROOK	60% STATE 40% OAKBROOK TERRACE	100% OAKBROOK TERRACE	100% OAKBROOK TERRACE	100% OAKBROOK TERRACE	100% OAKBROOK TERRACE
20100110	TREE REMOVAL (6 TO 15 UNITS)	UNIT	887	887													
20100210	TREE REMOVAL (OVER 15 UNITS)	UNIT	584	584													
20100500	TREE REMOVAL, ACRES	Acres	0.5	0.5													
20101100	TREE TRUNK PROTECTION	EACH	3	3													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	37,195	37,195													
20400800	FURNISHED EXCAVATION	CU YD	3,190	3,190													
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	5,189	5,189													
20800150	TRENCH BACKFILL	CU YD	9,716	8,372								1153	62				129
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	7,833	7,833													
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	31,852	31,852													
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	395	395													
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	395	395													
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	395	395													
25100115	MULCH, METHOD 2	ACRE	6	6													
25200110	SODDING, SALT TOLERANT	SQ YD	31,852	31,852													
25200200	SUPPLEMENTAL WATERING	UNIT	410	410													
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	604	604													
28000400	PERIMETER EROSION BARRIER	FOOT	4,565	4,565													
28000500	INLET AND PIPE PROTECTION	EACH	68	68													
28000510	INLET FILTERS	EACH	152	152													
28100107	STONE RIPRAP, CLASS A4	SQ YD	44	44													
28200200	FILTER FABRIC	SQ YD	60	60													
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	5,508	3,008							2,500						
35300300	PORTLAND CEMENT CONCRETE BASE COURSE, 8"	SQ YD	186	186													
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	2,199	2,199													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	146	146													
40600300	AGGREGATE (PRIME COAT)	TON	307	307													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5	5													
40600895	CONSTRUCTING TEST STRIP	EACH	4	4													
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	28	28													
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	355	355													
40600990	TEMPORARY RAMP	SQ YD	127	127													
42001300	PROTECTIVE COAT	SQ YD	6,673	6,673													

⊙ - DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.U. ROUTE 3545  
IL RTE 56 (BUTTERFIELD ROAD)

SUMMARY OF QUANTITIES

SCALE: NTS  
DATE: 2/20/04

DRAWN BY: SMP  
CHECKED BY: BDH