

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3545	54-WRS-7	DUPAGE	235	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 62291				

CODE NO.	ITEM	UNIT	URBAN		ROADWAY	TRAFFIC SIGNALS RTE 56 @ SUMMIT/MIDWEST RD	SUMMIT/MIDWEST PRE-EMPTION EQUIPMENT	TRAFFIC SIGNALS RTE 56 @ MYRTLE/MACARTHUR	MYRTLE/MACARTHUR PRE-EMPTION EQUIPMENT	TRAFFIC SIGNAL INTERCONNECT	SIDEWALK	BIKE PATH	OAK BROOK WATER MAIN	OAKBROOK TERRACE WATER MAIN	OAK BROOK SEWER UPGRADE	OAKBROOK TERRACE SEWER UPGRADE	HINSDALE SANITARY DISTRICT SEWER
			TOTAL QUANTITY	100% STATE 1000-2A	90% STATE 10% DUPAGE CO. Y031-1F	100% OAKBROOK TERRACE Y031-3D	90% STATE 10% OAKBROOK TERRACE Y031-1F	100% OAKBROOK TERRACE Y031-3D	100% STATE Y031-1F	50% STATE 50% OAKBROOK PARK DIST SFTY-1B	100% OAKBROOK TERRACE SFTY-1B	100% OAKBROOK TERRACE Y060	100% OAKBROOK TERRACE Y060	75% STATE 25% OAK BROOK Y060	60% STATE 40% TERRACE Y060	100% SANITARY DISTRICT	
X0323841	WATER MAIN LINE STOP, 8"	EACH	1											1			
X0487700	SANITARY SEWER REMOVAL 10"	FOOT	111														111
X0712400	TEMPORARY PAVEMENT	SQ YD	9,070	9,070													
X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	11	11													
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	1,999	1,999													
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	3,529	3,529													
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N 50	TON	1,163	892								271					
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX F, N 90	TON	6,606	6,606													
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N 50	TON	575	575													
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19, N 90	TON	33,359	33,359													
X4066670	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	TON	73	73													
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD) SUPERPAVE, IL 4.75, N50	TON	279	279													
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	942	942													
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	16	16													
X8050015	SERVICE INSTALLATION, POLE MOUNT	EACH	2			1		1									
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MMI2F SM12F	FOOT	5147						5,147								
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C (GREEN)	FOOT	1230			708		522									
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	657			347		310									
X8800020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8			4		4									
X8800040	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5			2		3									
X8800045	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	9			5		4									
X8800070	SIGNAL HEAD, L.E.D., 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1			1											
X8805280	SIGNAL HEAD, L.E.D., 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2			1		1									
X8810610	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	6			4		2									
X8810620	PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED	EACH	2			2											
49201718	CLASS D PATCHES, TYPE II, 6 1/2"	SQ YD	28	28													
49201721	CLASS D PATCHES, TYPE III, 6 1/2"	SQ YD	91	91													
49201724	CLASS D PATCHES, TYPE IV, 6 1/2"	SQ YD	485	485													
X0325012	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 10"	EACH	2									2					
X0325013	WATER SERVICE INSTALLATION, 1-1/2"	EACH	2									2					
X0325014	WATER SERVICE INSTALLATION, 2"	EACH	4									4					
54210027	PIPE CULVERTS, CLASS D, TYPE I, 27" (TEMPORARY)	FOOT	5	5													

⊙ - DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.U. ROUTE 3545  
 IL RTE 56 (BUTTERFIELD ROAD)

SUMMARY OF QUANTITIES

SCALE: NTS  
 DATE: 2/20/04

DRAWN BY: SMP  
 CHECKED BY: BDH