

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3545	54-WRS-7	DUPAGE	235	66
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62291				

DRAINAGE AND UTILITY STRUCTURE TABLES

STRUCT. NO.	STATION	OFFSET	STRUCTURE TYPE	RIM	INVERT			
					NORTH	SOUTH	EAST	WEST
S-198	96+64	38' R	CB TA 4' DIA T24 F&G	701.27	-	-	-	697.92
S-199	97+25	29' L	MAN TA 4' DIA T1F CL	702.10	696.40	696.30	697.78	-
S-200	97+25	23' L	CB TA 4' DIA T24 F&G	702.11	-	-	-	697.81
S-201	98+29	44' R	CB TA 4' DIA T24 F&G	702.91	-	-	-	698.65
S-202	98+46	24' L	CB TA 4' DIA T24 F&G	703.46	698.30	698.10	698.30	-

DRAINAGE AND UTILITY PIPE TABLES

NO.	LENGTH (FOOT)	MATERIAL	TYPE	DIA (IN.)	SLOPE %	TBF (CU. YD.)
P-197	3	SS, CL A	2	12	1.00	1.0
P-198	69	SS, CL A	2	12	0.50	2.2
P-199	14	SS, CL A	2	18	1.00	10.6

WATER MAIN STRUCTURE TABLES

STRUCT. NO.	STATION	OFFSET	STRUCTURE TYPE	RIM
W-8	96+15	16' R	10" VALVE IN 5' DIA VAULT, TIF CL	701.04
W-9	96+23	26' R	10" VALVE IN 5' DIA VAULT, TIF CL	700.92
W-10	100+49	3' R	10" VALVE IN 5' DIA VAULT, TIF CL	705.30
W-11	104+12	6' R	10" VALVE IN 5' DIA VAULT, TIF CL	710.31

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.U. ROUTE 3545 IL RTE 56 (BUTTERFIELD ROAD)
NAME	DATE	
		DRAINAGE AND UTILITY PIPE AND STRUCTURE TABLES

SCALE: NTS
DATE: 2/20/04
DRAWN BY: BCD
CHECKED BY: MGJ