

F.A.U. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3545	54-WRS-7	DUPAGE	235	68
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62291				

PIPE UNDERDRAINS, 4"

NO.	STATION	LENGTH (FEET)	OUTLET
U-26	17+31	76	S-203

DRAINAGE AND UTILITY STRUCTURE TABLES

STRUCT. NO.	STATION	OFFSET	STRUCTURE TYPE	RIM	INVERT			
					NORTH	SOUTH	EAST	WEST
S-203	17+03	19' L	MAN TA 4' DIA TIF CL	702.54	699.65	699.55	-	699.65
S-204	17+03	26' L	CB TC T&G	701.75	-	-	699.71	-
S-205	18+10	28' L	CB TC T&G	702.40	-	-	700.45	-
S-206	18+17	15' L	MAN TA 4' DIA TIF CL	703.79	700.32	700.22	-	700.32
S-207	21+43	12' L	MAN TA 4' DIA TIF CL	709.62	705.31	705.11	705.54	706.02
S-207A	21+43	26' L	INLET TA T&G	708.80	-	-	706.30	-
S-208	21+43	20' R	CB TA 4' DIA T24 F&G	709.46	-	-	-	705.86
S-209	22+99	7' L	MAN TA 4' DIA TIF CL	712.01	706.03	705.93	-	-
S-210	23+44	40' L	MAN TA 4' DIA T&G	710.00	-	706.25	-	-

DRAINAGE AND UTILITY PIPE TABLES

NO.	LENGTH (FOOT)	MATERIAL	TYPE	DIA (IN)	SLOPE %	TBF (CU. YD.)
P-200	6	SS, CL A	1	12	1.00	0.5
P-201	113	SS, CL A	1	15	0.50	29.3
P-202	13	SS, CL A	1	12	1.00	1.7
P-203	82	SS, CL A	1	15	3.35	3.0
P-204	98	SS, CL A	2	15	0.80	39.1
P-205	32	SS, CL A	1	12	1.00	10.3
P-206	14	SS (WMR)	1	12	2.00	2.8
P-207	156	SS, CL A	2	15	0.40	116.3
P-208	55	SS (WMR)	2	15	0.40	17.6

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.U. ROUTE 3545 IL RTE 56 (BUTTERFIELD ROAD)
NAME	DATE	
		DRAINAGE AND UTILITY PIPE AND STRUCTURE TABLES

SCALE: NTS
DATE: 2/20/04
DRAWN BY: BCD
CHECKED BY: BDH