

CODE NUMBER	ITEM	UNIT	URBAN TOTAL	ROADWAY		SIDEWALK		TRAFFIC SIGNALS					LIGHTING	WATER MAIN			SANITARY SEWER	
				100 % STATE	100 % STATE	50% STATE	50% STATE	FAIRVIEW	CASS	WOODSTOCK	MIDDAUGH	PROSPECT	INTERCONNECT	100 % WESTMONT	100% STATE	100% CLARENDON HILLS	63% STATE	100% DOWNERS
				J000-2A	J000-1B	50% WESTMONT	50% CLARENDON HILLS	100% STATE	90% STATE	90% STATE	90% STATE	93.3% STATE	100% STATE	100% STATE	100% STATE	3% CLARENDON HILLS	100% STATE	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	431	431				8.00										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	323	323														
20101000	TEMPORARY FENCE	FOOT	7,342	7,342														
20101100	TREE TRUNK PROTECTION	EACH	43	43														
20101700	SUPPLEMENTAL WATERING	UNIT	8	8														
20200100	EARTH EXCAVATION	CU YD	18,148	18,148														
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5,865	5,865														
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,571	3,571														
20800150	TRENCH BACKFILL	CU YD	13,346	12,842												504	1,361	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10,447	10,447														
25000210	SEEDING, CLASS 2A	ACRE	4.1	4.1														
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	500	500														
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	500	500														
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	500	500														
25200110	SODDING, SALT TOLERANT	SQ YD	10,447	10,447														
25200200	SUPPLEMENTAL WATERING	UNIT	32	32														
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	6.3	6.3														
28000400	PERIMETER EROSION BARRIER	FOOT	12,077	12,077														
28000510	INLET FILTERS	EACH	263	263														
28100105	STONE RIPRAP, CLASS A3	SQ YD	11	11														
35500300	BITUMINOUS BASE COURSE 6"	SQ YD	243	243														
35500500	BITUMINOUS BASE COURSE 8"	SQ YD	22	22														
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	8,595.8	8,595.8														
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1,798	1,798														
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	30	30														
42000301	PORTLAND CEMENT CONCRETE PAVEMENT, 8" (JOINTED)	SQ YD	43,198	43,198														
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	5,660	5,660														
42001300	PROTECTIVE COAT	SQ YD	76,448	76,448														
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	3,029	3,029														
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	3,714	3,714														

* = SPECIALTY ITEM



NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MAPLE AVENUE / CHICAGO AVENUE
SHEET 1 OF 10

SCALE: NONE
DATE: 31-MAR-2005

DRAWN BY: E.D.
CHECKED BY: G.T.