F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1487	66R	DuPAGE	412	10
STA. 23+00.00		TO STA. 144+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62376

	CODE NUMBER	ITEM	UNIT	URBAN TOTAL	ROADWAY	SIDEWALK			TRAFFIC SIGNALS						LIGHTING	WATER MAIN			SANITARY SEWER
					100 % STATE	~~100 % STATE~~	50% STATE 50% WESTMONT SFTY-1B	50% STATE 50% CLARENDON HILLS SFTY-1B	FAIRVIEW 100% STATE	CASS 90% STATE 10% WESTMONT	WOODSTOCK 90% STATE 10% CLARENDON HILLS	MIDDAUGH 90% STATE 10% CLARENDON HILLS	PROSPECT 93.3% STATE 6.7% CLARENDON HILLS	INTERCONNECT CASS AVE 100% STATE	100 % WESTMONT	~~100% STATE~~	100% CLARENDON HILLS	~~63% STATE 37% CLARENDON HILLS~~	~~100% OWNERS SANITARY DISTRICT~~
					J000-2A	~~J000-1B~~			Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y030-1E	~~Y060-~~	Y060-	~~Y060-~~	~~Y060-~~
	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2									2						
	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	12							6	4	2						
	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	5						4			1						
	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	4							2	1	1						
	87700140	TRAFFIC SIGNAL POST, GALVANIZED STEEL 20 FT.	EACH	1									1						
	87700150	STEEL MAST ARM ASSEMBLEY AND POLE, 22 FT.	EACH	1									1						
	87700160	STEEL MAST ARM ASSEMBLEY AND POLE, 24 FT.	EACH	1							1								
	87700170	STEEL MAST ARM ASSEMBLEY AND POLE, 26 FT.	EACH	3						1	1		1						
	87700180	STEEL MAST ARM ASSEMBLEY AND POLE, 28 FT.	EACH	1						1									
	87700190	STEEL MAST ARM ASSEMBLEY AND POLE, 30 FT.	EACH	1								1							
	87700210	STEEL MAST ARM ASSEMBLEY AND POLE, 34 FT.	EACH	2						1		1							
	87700230	STEEL MAST ARM ASSEMBLEY AND POLE, 38 FT.	EACH	1						1									
	87700240	STEEL MAST ARM ASSEMBLEY AND POLE, 40 FT.	EACH	1							1								
X	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	92						16	32	20	24						
	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	16						4	4	4	4						
	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	45							15	30							
	87900200	DRILL EXISTING HANDHOLE	EACH	1										1					
	88024120	OPTICALLY PROGRAMMED SIGNAL HEAD, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2							2								
	88024130	OPTICALLY PROGRAMMED SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4							4								
	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	24						8	8	4	4						
	88500100	INDUCTIVE LOOP DETECTOR	EACH	21						9	4	4	4						
	88600100	DETECTOR LOOP, TYPE 1	FOOT	337							190	147							
□	88700200	LIGHT DETECTOR	EACH	7							3	2	2						
□	88700300	LIGHT DETECTOR AMPLIFIER	EACH	3							1	1	1						
	88800100	PEDESTRIAN PUSH-BUTTON	EACH	22						8	6	6	2						
	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3						1	1	1							
Z	89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2						2									
Z	89501410	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT	EACH	1						1									
	89502200	MODIFY EXISTING CONTROLLER	EACH	1					1										
	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,381										1,381					

X = SPECIALTY ITEM
□ 100% CLARENDON HILLS

Z = 100 % Village of Westmont - Y031-30

Illinois Firm Registration No. 184-00633

Stanley Consultants INC.
8501 West Higgins Road, Suite 730
Chicago, Illinois 60631-2801
www.stanleygroup.com

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MAPLE AVENUE / CHICAGO AVENUE
SHEET 7 OF 10

SCALE: NONE
DATE: 21-MAR-2005

DRAWN BY: E.D.
CHECKED BY: G.T.

21-MAR-2005 O:\16524\sht\524csoql.dgn