


CODE NUMBER	ITEM	UNIT	URBAN TOTAL	ROADWAY		SIDEWALK			TRAFFIC SIGNALS					LIGHTING	WATER MAIN			SANITARY SEWER	
				100 % STATE	100 % STATE	50% STATE	50% STATE	FAIRVIEW	CASS	WOODSTOCK	MIDDAUGH	PROSPECT	INTERCONNECT	100 % WESTMONT	100% STATE	100% CLARENDON HILLS	100% STATE	100% DOWNERS SANITARY DISTRICT	
				J000-2A		50% WESTMONT SFTY-1B	50% CLARENDON HILLS SFTY-1B	100% STATE	90% STATE	90% STATE	90% STATE	93.3% STATE	100% STATE						
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1267								273	536	295	163					
X8800020	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	14								4	4	4	4					
X8800035	SIGNAL HEAD, L.E.D., 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	15									6	4	5					
X8800040	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4								4								
X8800045	SIGNAL HEAD, L.E.D., 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4								4								
X8800060	SIGNAL HEAD, L.E.D., 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2										2						
X8810610	PEDESTRIAN SIGNAL HEAD, L.E.D., 1-FACE, BRACKET MOUNTED	EACH	18								8	4	4	2					
X8810620	PEDESTRIAN SIGNAL HEAD, L.E.D., 2-FACE, BRACKET MOUNTED	EACH	4									2	2						
XX000406	BRICK PAVERS REMOVAL AND REPLACEMENT	SQ FT	2,394	2,394															
XX001484	ROOF DRAIN GUTTER OUTLET	EACH	4	4															
XX001490	GATE VALVES 8"	EACH	4	4															
XX002134	CONCRETE CURB AND GUTTER OUTLET SPECIAL	EACH	16	16															
XX002090	STAIR SIDE RAILING	FOOT	10	10															
XX002982	GATE VALVES 6"	EACH	8	8															
X XX002161	ABANDON EXISTING WATER MAIN	EACH	1	1															
X XX002852	RE-OPTIMIZED TRAFFIC SIGNAL SYSTEM	EACH	1																1
XX003032	GATE VALVES 12"	EACH	4	4															
XX003308	TRENCH DRAIN	FOOT	12	12															
XX003669	BITUMINOUS SIDEWALK REMOVAL	SQ YD	527	527															
XX004592	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	2	2															
X XX004698	WATER SERVICE TO BE ABANDONED	EACH	21	21															
X XX004786	ADJUSTMENTS, SPECIAL	EACH	57	57															
X XX005271	CONDUIT PUSHED, 2 1/2" DIAMETER, RIGID GALVANIZED STEEL	FOOT	200																200
X XX005293	CONCRETE HEADER BAND	FOOT	96	96															
X XX005402	CONDUIT IN TRENCH, 2 1/2" DIA., RIGID GALVANIZED STEEL	FOOT	750																750
X Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	60,311	60,311															
X Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1															
X Z0041700	PLUG EXISTING STORM SEWERS	EACH	6	6															
Z0064600	SELECTIVE CLEARING	ACRE	1.2	1.2															

X = SPECIALTY ITEM



NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
**MAPLE AVENUE / CHICAGO AVENUE**  
**SHEET 9 OF 10**

SCALE: NONE  
 DATE: 31-MAR-2005

DRAWN BY: E.D.  
 CHECKED BY: G.T.