F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1487	66R	DuPAGE	412	75
STA. 23+00.00		TO STA. 144+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62376

PIPE TABLE

PIPE NO.	STATION	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
1	23+62.0	23+80.0	CL A TY 2	12	23	5.66		23
2	23+80.0	23+80.0	CL A TY 2	12	4	1.11		4
3	23+80.0	27+42.0	CL A TY 2	18	358	257.76	25	333
4	26+55.0	26+55.0	CL A TY 1	12	5	0.66		5
5	26+55.0	26+55.0	CL A TY 1	12	17	2.24		17
6	31+25.0	28+94.0	CL A TY 3	48	222	542.79		222
7	27+20.0	27+42.0	CL A TY 1	12	20	2.84		20
8	27+20.0	27+42.0	CL A TY 1	12	25	3.80		25
9	27+38.0	27+42.0	CL A TY 2	ELLIPTICAL 48	22	24.35		22
10	28+76.0	27+42.0	CL A TY 2	48	130	148.07		130
11	27+38.0	27+50.9	CL A TY 2	48	44			44
12	27+50.9	27+57.9	CL A TY 1	48	46			46
13	27+57.9	27+69.1	CL A TY 1	ELLIPTICAL 48	34			34
14	28+93.6	28+94.0	CL A TY 2	21	12	14.48		12
15	27+85.0	27+85.0	CL A TY 2	12	5	1.08		5
16	28+94.0	29+12.0	CL A TY 2	12	22	5.65		22
17	31+25.0	31+25.0	CL A TY 2	12	4	1.15		4
18	31+25.0	31+25.0	CL A TY 2	12	14	4.04		14
19	33+60.0	31+25.0	CL A TY 3	48	231	832.99		231
20	28+94.0	29+00.0	CL A TY 2	12	6	1.61		6
21	73+85.0	74+10.0	CL A TY 1	12	22	2.90		22
22	98+87.0	99+05.0	CL A TY 2	12	15	4.49		15
23	99+05.0	100+06.0	CL A TY 2	12	97	29.00	21	76
24	124+00.0	124+00.0	CL A TY 2	12	28	10.72	20	8
25	129+95.0	129+90.0	CL A TY 2	12	26	8.05	20	6
26	34+85.0	34+85.0	CL A TY 2	12	4	1.15		4
27	34+85.0	34+85.0	CL A TY 2	15	15	10.40		15
28	35+50.0	34+85.0	CL A TY 2	12	62	21.79		62
29	35+57.0	34+85.0	CL A TY 2	12	69	14.84		69
30	36+35.0	36+35.0	CL A TY 3	12	10	9.52		10
31	36+35.0	36+35.0	CL A TY 3	12	20	19.05		20
32	37+45.0	37+45.0	CL A TY 3	12	10	8.88		10
33	37+87.0	34+85.0	CL A TY 3	48	298	910.39		298
34	37+86.9	37+87.0	CL A TY 2	24	10	15.39		10
35	41+60.0	37+87.0	CL A TY 2	48	369	559.40		369
36	37+45.0	37+45.0	CL A TY 2	12	20	17.76		20
37	40+20.0	40+20.0	CL A TY 2	12	17	4.90		17
38	40+08.0	40+08.0	CL A TY 2	12	5	1.55		5
39	41+40.0	41+40.0	CL A TY 1	12	17	2.24		17
40	48+75.0	47+10.0	CL A TY 3	36	161	552.94		161
41	43+90.0	41+60.0	CL A TY 2	42	226	143.85	20	206
42	41+60.0	41+60.0	CL A TY 1	12	4	0.53	4	
43	42+45.0	42+45.0	CL A TY 1	12	17	2.24		17

PIPE TABLE

PIPE NO.	STATION	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
44	42+63.0	42+63.0	CL A TY 1	12	5	0.66		5
45	45+68.0	43+90.0	CL A TY 3	42	174	311.70		174
46	45+67.8	45+68.0	CL A TY 2	12	10	12.25		10
47	46+30.0	46+30.0	CL A TY 2	12	16	5.12		16
48	46+30.0	46+30.0	CL A TY 2	12	4	1.15		4
49	47+10.0	46+30.0	CL A TY 3	36	76	240.37		76
50	41+71.1	41+60.0	CL A TY 1	15	45	5.45	45	
51	46+30.0	46+30.0	CL A TY 2	12	17	6.33		17
52	49+59.0	49+77.0	CL A TY 2	12	17	4.90		17
53	49+30.0	48+75.0	CL A TY 2	12	60	19.20		60
54	50+90.0	49+77.0	CL A TY 3	36	105	319.12		105
55	48+75.0	48+75.0	CL A TY 2	12	20	29.01		20
56	52+12.0	51+71.0	CL A TY 2	12	40	11.54		40
57	51+71.0	51+85.0	CL A TY 2	12	22	7.50		22
58	53+43.0	52+60.0	CL A TY 3	30	79	189.34		79
59	50+90.0	50+90.0	CL A TY 2	12	7	2.31		7
60	52+60.0	52+60.0	CL A TY 2	12	4	1.32		4
61	52+12.0	52+25.0	CL A TY 2	12	18	6.89		18
62	53+43.0	53+43.0	CL A TY 2	12	16	5.12		16
63	53+64.0	53+43.0	CL A TY 2	12	20	6.40		20
64	54+35.0	53+84.0	CL A TY 3	30	47	113.71		47
65	54+35.0	54+35.0	CL A TY 2	12	4	1.15		4
66	54+41.0	54+35.0	CL A TY 2	12	18	5.38		18
67	55+44.0	55+44.0	CL A TY 2	12	16	4.78		16
68	55+44.0	55+44.0	CL A TY 2	12	4	1.20		4
69	57+45.0	55+44.0	CL A TY 3	30	197	432.08		197
70	35+50.0	35+50.0	CL A TY 2	12	19	6.28		19
71	47+10.0	47+10.0	CL A TY 2	12	35	35.60		35
72	58+56.0	58+56.0	CL A TY 2	12	5	3.72		5
73	94+75.0	94+53.0	CL A TY 1	12	35	6.42		35
74	59+35.0	59+35.0	CL A TY 2	12	17	11.83		17
75	59+35.0	59+35.0	CL A TY 2	12	5	3.48		5
76	60+15.0	57+91.0	CL A TY 2	24	220	333.99		220
77	60+15.0	60+15.0	CL A TY 2	12	4	1.15		4
78	60+15.0	60+15.0	CL A TY 2	12	15	5.12		15
79	60+70.0	60+15.0	CL A TY 2	12	52	12.22		52
80	60+70.0	60+15.0	CL A TY 2	12	52	12.22		52
81	61+93.0	60+15.0	CL A TY 2	18	174	185.45		174
82	61+49.0	61+49.0	CL A TY 2	12	17	6.33		17
83	34+85.0	33+60.0	CL A TY 3	48	121	439.84		121
84	63+56.0	61+93.0	CL A TY 2	18	159	114.48	20	139
85	62+97.0	63+56.0	CL A TY 2	12	56	9.10		56
86	63+56.0	63+56.0	CL A TY 2	12	6	1.35		6

PIPE TABLE

PIPE NO.	STATION	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
87	63+56.0	63+56.0	CL A TY 2	12	17	3.83		17
88	62+97.0	63+56.0	CL A TY 2	12	56	9.10		56
89	64+80.0	63+56.0	CL A TY 2	12	120	34.62		120
90	64+20.0	64+80.0	CL A TY 1	12	57	9.26		57
91	64+80.0	64+80.0	CL A TY 2	12	7	1.43		7
92	64+20.0	63+56.0	CL A TY 2	12	61	9.91		61
93	64+80.0	64+80.0	CL A TY 2	12	19	4.09	10	9
94	65+38.0	64+80.0	CL A TY 1	12	55	8.36	55	
95	65+38.0	64+80.0	CL A TY 1	12	55	8.36		55
96	131+01.7	131+01.7	CL A TY 1	12	5	0.66		5
97	129+90.0	130+73.0	CL A TY 2	15	78	30.15		78
98	57+45.0	57+45.0	CL A TY 2	12	16	4.95		16
99	27+68.7	27+85.0	CL A TY 2	12	16	5.62		16
100	49+76.7	49+77.0	CL A TY 3	24	6	13.27		6
101	53+84.4	53+84.4	CL A TY 3	12	8	13.15		8
102	61+93.2	61+93.0	CL A TY 2	12	6	5.23		6
103	131+82.0	131+21.4	CL A TY 2	12	110	15.62	55	55
104	51+85.0	50+90.0	CL A TY 3	36	91	251.84		91
105	87+00.0	86+70.0	CL A TY 1	12	30	4.88	30	
106	92+65.0	92+65.0	CL A TY 2	12	36	11.14	20	16
107	93+00.0	93+00.0	CL A TY 1	12	21	7.16		21
108	52+60.0	51+85.0	CL A TY 3	30	71	170.17		71
109	27+85.0	27+85.0	CL A TY 2	12	17	3.66		17
110	27+00.0	27+20.0	CL A TY 1	12	17	2.24		17
200	65+80.4	65+64.4	CL A TY 2	12	50	10.23	22	28
201	66+73.9	67+75.0	CL A TY 2	12	98	21.07	98	
202	66+73.5	66+73.9	CL A TY 1	12	42	5.96	12	30
203	65+74.7	65+64.4	CL A TY 1	12	10	1.52		10
204	67+90.0	67+90.0	CL A TY 2	12	8	2.31		8
205	67+75.0	67+90.0	CL A TY 2	12	25	7.21	10	15
206	73+35.0	73+35.0	CL A TY 1	12	17	2.24	17	
207	73+43.0	73+43.0	CL A TY 1	12	5	0.66		5
208	67+90.0	70+74.0	CL A TY 2	12	280	104.30	25	255
209	69+25.0	69+25.0	CL A TY 2	12	6	1.67		6
210	39+75.0	39+75.0	CL A TY 2	12	26	9.14		26
211	27+00.0	27+20.0	CL A TY 1	12	17	2.24		17
212	69+25.0	69+25.0	CL A TY 2	12	18	5.00	10	8
213	74+17.4	74+10.0	CL A TY 1	12	4	0.61	4	
214	70+75.0	70+74.0	CL A TY 2	12	4	1.11		4
215	70+75.0	70+74.0	CL A TY 2	12	15	4.96		15
216	70+74.0	72+29.0	CL A TY 2	15	151	39.11		151
217	72+40.0	72+29.0	CL A TY 1	12	8	1.14		8
218	72+40.0	72+29.0	CL A TY 1	12	17	2.58	17	

Illinois Firm Registration No.:184-001533

Stanley Consultants INC.

8501 West Higgins Road, Suite 730
Chicago, Illinois 60631-2807
www.stanleygroup.com

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE STORM SEWER SCHEDULE
MAPLE AVENUE / CHICAGO AVENUE
SHEET 1 OF 3

SCALE: NONE — DRAWN BY: E.D.

DATE: 31-MAR-2005 — CHECKED BY: S.K.V.