F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1487	66R	DuPAGE	412	76
STA. 23+00.00		TO STA. 144+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 62376

PIPE TABLE

PIPE NO.	STATION	- STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
219	72+29.0	74+10.0	CL A TY 1	18	177	25.22		177
220	74+10.0	74+10.0	CL A TY 1	24	19	2.20	19	
221	74+10.0	74+10.0	CL A TY 1	12	4	0.53		4
222	73+69.0	74+10.0	CL A TY 1	12	40	5.28	40	
223	74+10.0	74+09.6	CL A TY 1	24	111	14.54		111
224	74+25.0	74+17.4	CL A TY 1	12	8	1.55		8
225	75+68.0	74+10.0	CL A TY 1	24	150	19.65		150
226	74+60.0	74+60.0	CL A TY 1	12	5	0.66		5
227	74+75.0	74+75.0	CL A TY 1	12	17	2.24		17
228	75+40.0	75+40.0	CL A TY 1	12	17	2.24		17
229	76+35.0	76+35.0	CL A TY 1	12	17	2.24		17
230	75+40.0	75+40.0	CL A TY 1	12	5	0.66		5
231	76+35.0	76+35.0	CL A TY 1	12	5	0.66		5
232	77+75.0	75+68.0	CL A TY 2	21	203	55.83	25	178
233	77+75.0	77+75.0	CL A TY 1	12	4	0.69		4
234	77+50.0	77+75.0	CL A TY 1	12	24	5.90	24	
235	79+32.0	77+75.0	CL A TY 2	21	153	58.91		153
236	78+95.0	78+95.0	CL A TY 2	12	5	0.81		5
237	78+95.0	78+95.0	CL A TY 2	12	17	4.00		17
238	79+00.0	78+95.0	CL A TY 1	12	17	4.18	17	
239	79+20.5	79+32.0	CL A TY 1	12	25	3.30	15	10
240	79+80.0	79+80.0	CL A TY 2	12	17	4.18		17
241	79+80.0	79+80.0	CL A TY 2	12	5	1.23		5
242	80+55.0	80+55.0	CL A TY 2	12	5	1.23		5
243	73+55.0	73+69.0	CL A TY 1	12	12	2.45		12
244	80+00.0	79+80.0	CL A TY 2	12	24	7.93	24	
245	80+55.0	80+55.0	CL A TY 2	12	17	4.18		17
246	81+59.0	79+32.0	CL A TY 2	21	223	118.19		223
247	74+10.0	74+10.0	CL A TY 1	24	39	4.52		39
248	130+73.0	130+73.3	CL A TY 2	18	13			13
249	81+45.0	81+59.0	CL A TY 1	12	12	1.58		12
250	81+45.0	81+59.0	CL A TY 1	12	19	2.51		19
251	83+08.0	81+59.0	CL A TY 2	21	145	53.87	15	130
252	82+80.0	82+80.0	CL A TY 2	12	17	2.58		17
253	82+80.0	82+80.0	CL A TY 2	12	5	0.76		5
254	70+30.9	70+75.0	CL A TY 2	12	40	14.06		40
255	57+65.0	57+45.0	CL A TY 2	12	20	5.98		20
256	49+77.0	48+75.0	CL A TY 3	36	98	326.89		98
257	201+19.4	201+38.4	CL A TY 1	12	25	4.33	25	
258	84+15.0	84+15.0	CL A TY 1	12	30	3.96		30
259	26+10.0	26+10.0	CL A TY 1	12	17	2.24		17
260	26+10.0	26+10.0	CL A TY 1	12	5	0.66		5
261	84+15.0	84+82.0	CL A TY 2	12	63	10.24		63

PIPE TABLE

PIPE NO.	STATION	- STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
262	85+77.0	84+82.0	CL A TY 1	ELLIPTICAL 30	90	18.72		90
263	84+82.0	84+70.0	CL A TY 1	ELLIPTICAL 30	21	7.26		21
264	53+84.0	53+43.0	CL A TY 3	30	37	89.51		37
265	33+16.5	33+39.9	CL A TY 1	12	25	3.55	25	
266	33+39.9	33+60.0	CL A TY 2	12	54	35.86		54
267	95+15.0	95+20.4	CL A TY 1	12	41	9.64		41
268	86+70.0	86+70.0	CL A TY 1	12	9	1.19		9
269	86+70.0	86+70.0	CL A TY 1	12	21	2.77		21
270	87+77.0	87+77.0	CL A TY 1	12	7	0.92		7
271	87+77.0	87+77.0	CL A TY 1	12	19	2.51		19
272	87+77.0	85+77.0	CL A TY 1	21	196	43.12	20	176
273	88+30.0	88+30.0	CL A TY 1	12	23	4.46		23
274	88+70.0	88+70.0	CL A TY 1	12	6	0.79		6
275	90+10.0	87+77.0	CL A TY 2	21	229	62.98		229
276	88+70.0	88+70.0	CL A TY 1	12	18	2.38		18
277	90+10.0	90+10.0	CL A TY 1	12	4	0.82		4
278	90+10.0	90+10.0	CL A TY 1	12	15	2.75		15
279	90+30.0	90+10.0	CL A TY 1	12	22	6.12		22
280	91+87.0	90+10.0	CL A TY 2	18	173	70.58		173
281	91+70.0	91+87.0	CL A TY 1	12	28	8.67		28
282	94+00.0	91+87.0	CL A TY 2	15	209	71.16	20	189
283	93+65.0	94+00.0	CL A TY 1	12	32	4.86		32
284	93+65.0	94+00.0	CL A TY 1	12	32	4.86	32	
285	94+00.0	94+00.0	CL A TY 2	12	15	3.23	15	
286	94+53.0	94+53.0	CL A TY 1	12	17	2.24	17	
287	94+00.0	94+00.0	CL A TY 2	12	4	0.82		4
288	94+53.0	94+53.0	CL A TY 1	12	5	0.66		5
289	95+20.0	95+20.0	CL A TY 2	12	5	0.87		5
290	95+20.4	95+20.4	CL A TY 2	12	20	3.46	20	
291	96+30.0	94+00.0	CL A TY 2	15	226	68.93		226
292	96+30.0	96+30.0	CL A TY 2	12	4	1.15		4
293	55+44.0	54+35.0	CL A TY 3	30	105	251.66		105
294	96+30.0	96+30.0	CL A TY 2	12	15	4.49	15	
295	57+91.0	57+45.0	CL A TY 2	30	42	82.67		42
296	112+71.7	130+00.0	CL A TY 2	36	37	53.05		37
297	34+25.0	34+85.0	CL A TY 2	12	57	19.44		57
298	42+20.0	42+45.0	CL A TY 1	12	23	3.04		23
299	43+40.0	43+40.0	CL A TY 1	12	17	2.24		17
300	99+05.0	99+05.0	CL A TY 2	12	15	4.33	15	
301	100+15.0	100+06.0	CL A TY 2	12	7	1.36		7
302	100+15.0	100+06.0	CL A TY 2	12	17	3.30	17	
303	100+06.0	102+00.0	CL A TY 2	12	190	54.82		190
304	101+95.0	102+00.0	CL A TY 2	12	17	4.73	17	

PIPE TABLE

PIPE NO.	STATION	- STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
305	102+00.0	102+00.0	CL A TY 2	12	4	1.11		4
306	102+00.0	104+13.0	CL A TY 2	12	209	53.71		209
307	104+08.0	104+13.0	CL A TY 1	12	16	2.77	16	
308	104+08.0	104+13.0	CL A TY 1	12	5	0.87		5
309	104+13.0	106+16.0	CL A TY 2	15	199	37.81	35	164
310	105+25.0	105+25.0	CL A TY 1	12	17	2.24	17	
311	46+30.0	45+68.0	CL A TY 3	36	58	154.78		58
312	106+16.0	106+16.0	CL A TY 1	12	4	0.53		4
313	106+40.0	106+40.0	CL A TY 1	12	17	2.24	12	5
314	108+80.0	108+80.0	CL A TY 1	12	19	2.51	12	7
315	108+19.0	110+23.0	CL A TY 2	18	200	48.70		200
316	109+35.0	109+35.0	CL A TY 2	12	19	2.51	12	7
317	108+80.0	108+80.0	CL A TY 1	12	10	1.32		10
318	109+35.0	109+35.0	CL A TY 2	12	10	1.42		10
319	110+23.0	110+23.0	CL A TY 2	12	8	1.47		8
320	110+23.0	110+23.0	CL A TY 2	12	17	2.94	12	5
321	58+49.0	58+49.0	CL A TY 2	12	17	12.92		17
323	111+20.0	111+20.0	CL A TY 1	12	19	2.51	12	7
324	111+20.0	111+20.0	CL A TY 1	12	10	1.32		10
325	111+65.0	111+65.0	CL A TY 1	12	19	2.51	12	7
326	111+65.0	111+65.0	CL A TY 1	12	10	1.32		10
327	112+00.0	112+22.6	CL A TY 1	12	20	2.84	20	
328	110+23.0	112+32.0	CL A TY 2	24	205	69.29		205
329	112+00.0	112+22.6	CL A TY 1	12	20	2.84		20
330	112+22.6	112+32.0	CL A TY 2	12	18	3.68	18	
331	112+50.0	112+50.0	CL A TY 1	12	19	3.49	12	7
332	112+22.6	112+32.0	CL A TY 2	12	10	2.05		10
333	112+32.0	113+00.0	CL A TY 2	24	64	54.09		64
334	113+00.0	113+00.0	CL A TY 2	36	17	21.43	17	
335	106+16.0	108+19.0	CL A TY 1	ELLIPTICAL 18	199	32.24		199
336	49+93.3	49+67.3	CL A TY 2	12	25	9.05		25
337	50+90.0	50+90.0	CL A TY 2	12	20	6.61		20
338	51+44.0	51+90.0	CL A TY 2	12	43	11.50	43	
339	51+90.0	51+85.0	CL A TY 2	12	8	2.73		8
340	52+60.0	52+60.0	CL A TY 2	12	16	5.46		16
341	113+00.0	113+03.2	CL A TY 2	36	17	18.91		17
342	113+30.0	113+30.0	CL A TY 1	12	10	1.32		10
343	113+70.0	113+70.0	CL A TY 1	12	19	2.51	12	7
344	112+75.0	112+75.0	CL A TY 2	12	10	3.10		10
345	114+00.0	114+00.0	CL A TY 1	12	10	1.32		10
346	114+80.0	113+00.0	CL A TY 2	12	176	30.45		176
347	114+40.0	114+40.0	CL A TY 1	12	19	2.51	12	7
348	114+90.0	114+80.0	CL A TY 1	12	12	1.58		12

Illinois Firm Registration No.:184-00533

Stanley Consultants INC.

850 West Higgins Road, Suite 730
Chicago, Illinois 60631-2801
www.stanleygroup.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE STORM SEWER SCHEDULE
MAPLE AVENUE / CHICAGO AVENUE
SHEET 2 OF 3

SCALE: NONE — DRAWN BY: E.D.

DATE: 02-FEB-2005 — CHECKED BY: S.K.V.