

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 305	1518 PCC-PC-2	COOK	17	12

CONTRACT 62457

PATCHING SCHEDULE NOTES AND INFORMATION

WILLOW ROAD
W. OF PHINGSTEN RD. TO E. OF IL 43., STA 47+00 TO STA.194+00

NOTES

1. The Engineer Shall Contact LOUIE SALAS, Technician, at the NORTHBROOK Maintenance Yard, (847) 272-1246, regarding patching locations.
2. The Engineer shall obtain approval from the District One Bureau Chief of Maintenance for any proposed revisions in the scheduled pavement patching locations.

PAVEMENT PATCHING SUMMARY

Pavement Patching (sq. yd.): WILLOW ROAD Eastbound

	LANE 1	LANE 2	Subtotal
Class B Patches, Type I 10"	0	0	0
Class B Patches, Type II 10"	809	858	1667
Class B Patches, Type III 10"	40	20	60
Class B Patches, Type IV 10"	0	0	0

Pavement Patching (sq. yd.): WILLOW ROAD Westbound

	LANE 1	LANE 2	Subtotal
Class B Patches, Type I 10"	0	0	0
Class B Patches, Type II 10"	645	651	1296
Class B Patches, Type III 10"	106	70	176
Class B Patches, Type IV 10"	96	94	190

Total Pavement Patching (sq. yd.): WILLOW ROAD

	Eastbound	Westbound	TOTAL
Class B Patches, Type I 10"	0	0	0
Class B Patches, Type II 10"	1667	1296	2963
Class B Patches, Type III 10"	60	176	236
Class B Patches, Type IV 10"	0	190	190
			3389

ILLINOIS DEPARTMENT OF TRANSPORTATION

WILLOW RD.
PAVEMENT PATCHING SCHEDULE