

CONTRACT NO. 62675

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	129	129			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22			
40600300	AGGREGATE (PRIME COAT)	TON	107	107			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	6	6			
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	360	360			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	280	280			
42001300	PROTECTIVE COAT	SQ YD	210	210			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6"	SQ YD	40	40			
44000116	BITUMINOUS REMOVAL OVER PATCHES, 4"	SQ YD	795	795			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	75	75			
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	10	10			
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	425	425			
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	75	75			
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	160	160			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	513	513			
55039700	STORM SEWERS TO BE CLEANED	FOOT	2500	2500			
60266600	VALVE BOXES TO BE ADJUSTED	EACH	22	22			
60300310	FRAMES AND LID TO BE ADJUSTED (SPECIAL)	EACH	38	38			
60404940	FRAMES AND GRATES, TYPE 23	EACH	8	8			
60406100	FRAMES AND LIDS, TYPE I CLOSED LID	EACH	5	5			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3150	3150			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	270	270			
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	40461	40461			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	1000			
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	3000	3000			
70300645	TEMPORARY PAINT PAVEMENT MARKING LINE 12"	FOOT	700	700			
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	800	800			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	525	525			
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	270	270			
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40461	40461			
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3000	3000			
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	700	700			
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	800	800			
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	650	650			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	425	425			
81400115	HANDHOLE TO BE ADJUSTED	EACH	4	4			
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	2477	2477			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
X3550300	BITUMINOUS BASE COURSE, SUPERPAVE, 6"	SQ YD	425	425			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	4695	4695			
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C" N50	TON	50	50			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	2350	2350			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	53741	53741			
XX001306	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	400	400			
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	13	13			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	17	17			
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	4	4			

*SPECIALITY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
WOOD STREET
IL 83 TO 161ST STREET
SUMMARY OF QUANTITIES

Rev.

PLOT DATE: 3/28/2005

3/28/2005 10:10:10 AM