

CONTRACT NO. 62694
F.A.I. ROUTE 94 (DAN RYAN EXPRESSWAY)
71ST STREET TO I-57 (NB RAMPS, C-D'S, AND RETAINING WALLS)
COOK COUNTY

SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	7
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (1516.1, 1717 & 1818) R-8				

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE						
				DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007	
20100110	TREE REMOVAL (6-15 UNITS DIAMETER)	UNIT	1511	1511						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	400	400						
20101000	TEMPORARY FENCE	FOOT	8148	8148						
20200100	EARTH EXCAVATION	CU YD	80615	80615						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12265	12265						
20400800	FURNISHED EXCAVATION	CU YD	606	606						
20700220	POROUS GRANULAR EMBANKMENT	CU YD	3020	440			29			2551
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	410	410						
20800150	TRENCH BACKFILL	CU YD	12888	12888						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	27728	27728						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	67542	67542						
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	11416	11416						
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	11416	11416						
* 25000210	SEEDING, CLASS 2A	ACRE	16.25	16.25						
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1463	1463						
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1463	1463						
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1463	1463						
⊙ * 25000750	MOWING	ACRE	29.50	29.50						
* 25100630	EROSION CONTROL BLANKET	SQ YD	77917	77917						
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1130	1130						
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	3256	3256						
28000300	TEMPORARY DITCH CHECKS	EACH	71	71						
* 28000400	PERIMETER EROSION BARRIER	FOOT	16889	16889						
* 28000510	INLET FILTERS	EACH	90	59	31					
28001000	AGGREGATE (EROSION CONTROL)	TON	13	13						
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	8378		8378					
31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	2274	2274						
31101860	SUB-BASE GRANULAR MATERIAL, TYPE B 24"	SQ YD	25454	25454						
31200100	STABILIZED SUB-BASE 4"	SQ YD	23672	23672						
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	4969		4969					
35300510	PORTLAND CEMENT CONCRETE BASE COURSE 10 1/2"	SQ YD	2422		2422					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.9		5.9					

- * - SPECIALTY ITEM
- - IDOT PAY CODE SFTY-3N
- △ - IDOT PAY CODE Y080
- ⊙ - NON-PARTICIPATING

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 1 OF 10

SCALE: NONE
DATE: MARCH 18, 2005
DRAWN BY: MPG
CHECKED BY: JPA

P:\02-37-35\Road\CI\70's\sq\As\01-30.dgn 05/09/2005 04:52:29 PM