F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	8
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
				DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
40600300	AGGREGATE (PRIME COAT)	TON	30		30				
40600895	CONSTRUCTING TEST STRIP	EACH	2		2				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	9		9				
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2529	2529					
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	17322	17322					
42001300	PROTECTIVE COAT	SQ YD	32349	30161	2188				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	2402		2402				
44000100	PAVEMENT REMOVAL	SQ YD	21600	14227	7373				
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	140		140				
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	21252	16573	4679				
44001980	CONCRETE BARRIER REMOVAL	FOOT	1096	1096					
44004250	PAVED SHOULDER REMOVAL	SQ YD	8112	6726	1386				
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	233	233					
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	637	351	286				
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	1289	1289					
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	121		121				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1						1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1						1
50102400	CONCRETE REMOVAL	CU YD	10			7			3
50104650	SLOPE WALL REMOVAL	SQ YD	202	146					56
50200100	STRUCTURE EXCAVATION	CU YD	9028	117	95	45			8771
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	130	130					
50200410	ROCK EXCAVATION FOR STRUCTURES (SPECIAL)	CU YD	31	31					
50300225	CONCRETE STRUCTURES	CU YD	4083	50	44	24			3965
50300300	PROTECTIVE COAT	SQ YD	10492		52	30			10410
50300510	RUSTICATION FINISH	SQ FT	41695		60	12			41623
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6370						6370
50500505	STUD SHEAR CONNECTORS	EACH	11836						11836
* 50700209	UNTREATED TIMBER LAGGING	SQ FT	49261						49261
* 50700211	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	4399						4399
* 50700213	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	FOOT	161						161
* 50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	31347						31347

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

REVISIONS NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 2 OF 10

SCALE: NONE DRAWN BY: MPG

DATE: MARCH 18, 2005 CHECKED BY: JPA

p:\02373\road\al\asqt\asf02sq.dgn 05/09/2005 03:33:07 PM