F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	11
STA. 2200+00.00	TO STA. 2362+00.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
					DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	565.5	565.5					
	60605500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	11.5		11.5				
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	195.0	79.0	116.0				
	60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	311.0	311.0					
	60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	8860	8860					
*	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	587.5	587.5					
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2					
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2					
*	63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4	4					
	63200310	GUARDRAIL REMOVAL	FOOT	828	402	426				
	63700805	CONCRETE BARRIER TRANSITION	FOOT	313	313					
	66400305	CHAIN LINK FENCE, 6'	FOOT	3492	392	3100				
	66410300	CHAIN LINK FENCE REMOVAL	FOOT	7337		7337				
	66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	20			20			
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	26870	26870					
*	66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	6	6					
	67100100	MOBILIZATION	L SUM	1	0.5	0.5				
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	0.5	0.5				
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	2		2				
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60		60				
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	18210	12490	5720				
	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	407		407				
	70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	8508		8508				
	70300540	PAVEMENT MARKING TAPE, TYPE III, 6"	FOOT	850		850				
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	14243	10575	3668				
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	19130	13660	5470				
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	8670	7350	1320				
*	72000100	SIGN PANEL - TYPE 1	SQ FT	30				30		
*	72000200	SIGN PANEL - TYPE 2	SQ FT	234				234		
*	72000300	SIGN PANEL - TYPE 3	SQ FT	3944				3944		
*	72100100	SIGN PANEL OVERLAY	SQ FT	44				44		

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 5 OF 10

SCALE: NONE DRAWN BY: MPG

DATE: MARCH 18, 2005 CHECKED BY: JPA

p:\0237.3\road\o170\sgl\ash05sa01.dgn
05/09/2005 03:33:09 PM