F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	14
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
					DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
	X4420223	CLASS C PATCHES, TYPE II, 10 1/2 INCH	SQ YD	50		50				
	60608530	COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.48	FOOT	233.0	233.0					
	X6063605	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.24 (VARIABLE WIDTH GUTTER FLAG)	FOOT	239.0	63.0	176.0				
*	X0324976	CONDUIT DIRECTIONAL BORED, 6" DIA., HDPE	FOOT	614			614			
*	X0324977	CONDUIT ENCASED, REINFORCED CONCRETE, 2 - 4" DIA. CNC AND 1 - 2" DIA. CNC, 2 WIDE X 2 HIGH	FOOT	31			31			
*	X0324978	CONDUIT ENCASED, REINFORCED CONCRETE, 2" DIA., CNC	FOOT	451			451			
*	X0324989	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 2" DIA., CNC 2 WIDE X 2 HIGH	FOOT	123			123			
*	X0324980	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA. CNC AND 1 - 2" DIA. CNC, 2 WIDE X 2 HIGH	FOOT	131			131			
*	X0324981	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA. CNC AND 1 - 3" DIA. CNC, 2 WIDE X 2 HIGH	FOOT	80			80			
*	X0324982	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA. CNC AND 3 - 2" DIA. CNC, 2 WIDE X 3 HIGH	FOOT	64			64			
*	X0324983	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA. CNC AND 6 - 2" DIA. CNC, 2 WIDE X 5 HIGH	FOOT	95			95			
*	X0324979	CONDUIT ENCASED, REINFORCED CONCRETE, 3" DIA., CNC	FOOT	19			19			
*	X0324984	CONDUIT ENCASED, REINFORCED CONCRETE, 5 - 4" DIA. CNC AND 1 - 2" DIA. CNC, 2 WIDE X 3 HIGH	FOOT	576			576			
*	X0324985	CONDUIT ENCASED, REINFORCED CONCRETE, 5 - 4" DIA. CNC AND 2 - 2" DIA. CNC, 2 WIDE X 4 HIGH	FOOT	84			84			
*	X0324986	CONDUIT ENCASED, REINFORCED CONCRETE, 5 - 4" DIA. CNC AND 3 - 2" DIA. CNC, 2 WIDE X 4 HIGH	FOOT	564			564			
*	X0324987	CONDUIT ENCASED, REINFORCED CONCRETE, 5 - 4" DIA. CNC AND 6 - 2" DIA. CNC, 2 WIDE X 6 HIGH	FOOT	380			380			
	60248690	JUNCTION CHAMBER NO. 61	EACH	1	1					
	60248692	JUNCTION CHAMBER NO. 62	EACH	1	1					
	X6022120	MANHOLES, DROP TYPE, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3					
	X6022130	MANHOLES, DROP TYPE, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
	X6024800	MODIFIED JUNCTION CHAMBER	EACH	1						1
	44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	111	111					
*	X0324988	RELOCATE CITY STREET LIGHT POLE	EACH	10			10			
	X0320816	SLEEPER SLAB	SQ YD	204	204					
*	E20200G1	VINE-PARTHENOCISSUS QUINQUEFOLIA (VIRGINIA CREEPER), 1-GALLON POT	EACH	1101	1101					
*	K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	12	12					
	X0300057	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	4	4					
	X0320870	BRACED EXCAVATION	CU YD	748	513		17			218
	X0321720	WATER MAIN REMOVAL	FOOT	3783	3783					
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	208		208				
	X0322400	PILE EXTRACTION	EACH	3						3
	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1550	1550					

* - SPECIALTY ITEM
□ - IDOT PAY CODE SFTY-3N
△ - IDOT PAY CODE Y080
⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 8 OF 10

SCALE: NONE DRAWN BY: MPG
DATE: MARCH 18, 2005 CHECKED BY: JPA

p:\0237 3\road\a170sqt\ts1083.dgn
05/09/2005 03:33:11 PM