| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 94 | * | COOK | 860 | 15 |
| STA. 2200+00.00 | TO STA. 2362+00.00 | | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

* (1516.1, 1717 & 1818) R-8

62694

# SUMMARY OF QUANTITIES

| | CODE NUMBER | ITEM DESCRIPTION | UNIT | TOTAL | URBAN - 90% FEDERAL, 10% STATE | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | DAN RYAN J000-2A | FRONTAGE RD I000-2A | LIGHTING Y030-1E | SIGNING Y002-1C | I.T.S. Y032-1F | STRUCTURAL Y007 |
| * | X0322859 | WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE | POUND | 22 | 22 | | | | | |
| | X0323426 | SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING | EACH | 180 | 118 | 62 | | | | |
| * | X0323574 | MAINTENANCE OF LIGHTING SYSTEM | CAL MO | 18 | | | 18 | | | |
| * | X0323907 | COMMUNICATIONS VAULT | EACH | 6 | | | | | 6 | |
| | X0324112 | BARRIER BASE | FOOT | 2003 | 2003 | | | | | |
| * | X0324209 | CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA., CNC 2 WIDE X 2 HIGH | FOOT | 86 | | | 86 | | | |
| * | X0324210 | CONDUIT ENCASED, REINFORCED CONCRETE, 4 - 4" DIA., CNC 2 WIDE X 2 HIGH | FOOT | 76 | | | 76 | | | |
| * | X0324211 | CONDUIT ENCASED, REINFORCED CONCRETE, 5 - 4" DIA., CNC 2 WIDE X 3 HIGH | FOOT | 38 | | | 38 | | | |
| * | X0324212 | CONDUIT ENCASED, REINFORCED CONCRETE, 6 - 4" DIA., CNC 2 WIDE X 3 HIGH | FOOT | 85 | | | 85 | | | |
| * | X0324219 | CONDUIT ENCASED, REINFORCED CONCRETE, 2 - 4" DIA., CNC 2 WIDE X 1 HIGH | FOOT | 306 | | | 306 | | | |
| | X0324433 | LIGHT TOWER SERVICE PAD, 6" | SQ FT | 137 | 137 | | | | | |
| * | X0324455 | DRILLING AND SETTING SOLDIER PILES (IN SOIL) | CU FT | 210013 | | | | | | 210013 |
| * | X0324456 | DRILLING AND SETTING SOLDIER PILES (IN ROCK) | CU FT | 116 | | | | | | 116 |
| | X0324697 | SOIL STABILIZERS | POUND | 29000 | 29000 | | | | | |
| | X0324698 | APPLYING DUST SUPPRESSION AGENT | UNIT | 11 | 11 | | | | | |
| * | X0324863 | COMBINED SEWERS, ESVCP, TYPE 2, 8" | FOOT | 7 | | 7 | | | | |
| | X0324864 | DRAIN CONNECTIONS | FOOT | 83 | | 83 | | | | |
| | X0712400 | TEMPORARY PAVEMENT | SQ YD | 12721 | 12721 | | | | | |
| | X4021000 | TEMPORARY ACCESS (PRIVATE ENTRANCE) | EACH | 5 | | 5 | | | | |
| | X4022000 | TEMPORARY ACCESS (COMMERCIAL ENTRANCE) | EACH | 5 | | 5 | | | | |
| | X4023000 | TEMPORARY ACCESS (ROAD) | EACH | 5 | | 5 | | | | |
| | X4066426 | BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 | TON | 823 | | 823 | | | | |
| | X4067100 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50 | TON | 427 | | 427 | | | | |
| | X6061001 | COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.48 | FOOT | 5933.5 | 5933.5 | | | | | |
| | X6063401 | COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.12 | FOOT | 6379.5 | 6379.5 | | | | | |
| | X6063600 | COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.24 | FOOT | 5745.5 | 4625.5 | 1120.0 | | | | |
| | X6065740 | CONCRETE MEDIAN SURFACE, 5" (MODIFIED) | SQ FT | 9060 | | 9060 | | | | |
| | X6370920 | CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT | FOOT | 1199 | 1199 | | | | | |
| | X6370930 | CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT | FOOT | 491 | 491 | | | | | |
| | X6640210 | TEMPORARY CHAIN LINK FENCE (PORTABLE) | FOOT | 11279 | | 11279 | | | | |
| | X6700410 | ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL) | CAL MO | 15 | 15 | | | | | |
| | X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | L SUM | 1 | 1 | | | | | |

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

| REVISIONS | |
|---|---|
| NAME | DATE |
| REVISED | 05/06/05 |
| REVISED | 04/15/05 |

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 9 OF 10

SCALE: NONE | DRAWN BY: MPG

DATE: MARCH 18, 2005 | CHECKED BY: JPA