F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	672
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

PROPOSED GROUND-MOUNTED SIGN SCHEDULE

LOCATION	STATION	SIGN				SUPPORT				SIGN REMARKS
		TYPE	WIDTH, FT	HEIGHT, FT	AREA, SQ FT	TYPE	POST QUANTITY	POST LENGTH (FT)	CONCRETE FND. (CY)	
NB I-57 (BISHOP FORD)	214+56	2	3	4	12	WOOD	1	16		R2-1 (55 MPH)
NB I-94 (DAN RYAN)	2203+00	2	4.5	4.5	20.25	WOOD	2	33		AIS 3/4 MILE
NB I-94 (DAN RYAN)	2211+20	2	3	4	12	WOOD	1	16		R2-1 (55 MPH)
NB I-94 (DAN RYAN)	2332+10	2	4.5	4.5	20.25	WOOD	2	33		AIS 1/4 MILE
NB I-94 (DAN RYAN)	2240+53	3	4.5	6	27	WOOD	2	36		87TH ST AIS & ARROW
NB I-94 (DAN RYAN)	2241+92	2	3	4	12	WOOD	1	16		W13-3 (RAMP 30 MPH)
NB 87TH ST. RAMP	8723+42	1	2.5	2.5	6.25	WOOD	1	14.5		R5-1
NB 87TH ST. RAMP	8724+88	3	5.5	5	27.5	WOOD	2	34		87TH ST AIS INFO
NB 87TH ST. RAMP	8726+92	1	1.5	1.5	2.25	WOOD	1	13.5		R1-1
NB I-94 (DAN RYAN)	2257+00	2	3	4	12	WOOD	1	16		R2-1 (55 MPH)
NB I-94 (DAN RYAN)	2308+57	2	4.5	4.5	20.25	WOOD	2	33		AIS 3/4 MILE
NB I-94 (DAN RYAN)	2312+30	2	3	4	12	WOOD	1	16		R2-1 (55 MPH)
NB I-94 (DAN RYAN)	2325+50	3	19.5	14.5	282.75	STEEL BREAKAWAY	3	76.25	3.82	EXIT 59B TO 90 E. SKYWAY CHICAGO SKYWAY VIA STATE ST 3/4 MILE
NB I-94 (DAN RYAN)	2331+50					WOOD	1	17		EXISTING "TRUCKS USE 2 RIGHT LANES"
NB I-94 (DAN RYAN)	2336+50	2	4.5	4.5	20.25	WOOD	2	33		AIS 1/4 MILE
NB I-94 (DAN RYAN)	2342+50	2	3	4	12	WOOD	1	16		W13-3 (RAMP 30 MPH)
NB I-94 (DAN RYAN)	2347+12	2	4	4	16	WOOD	1	17.66		W4-3R
NB I-94 (DAN RYAN)	2348+44	2	3.5	4.67	16.35	TELES. STEEL	1	9		EXIT 59C (1 ARROW)
NB 71ST ST. RAMP	8409+00	1	2.5	2.5	6.25	WOOD	1	14.5		R5-1
NB 71ST ST. RAMP	8410+40	3	5.5	5	27.5	WOOD	2	34		71ST ST AIS INFO
NB I-94 (DAN RYAN)	2352+67	1	3	3	9	TELES. STEEL	1	8.57		W4-1R
NB I-94 (DAN RYAN)	2355+00	3	7.5	5	37.5	WOOD	2	34		EXIT 59C & ARROW
NB 71ST ST. RAMP	8412+52	1	2.5	2.5	6.25	WOOD	1	14.5		R1-1
NB I-94 (DAN RYAN)	2359+76	3	16	12.5	200	STEEL BREAKAWAY	2	46.88	2.55	TO INT. 90 EAST TOLLWAY SKYWAY VIA STATE ST EXIT 59B

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

PROPOSED SIGNING SCHEDULE
SHEET 2 OF 2

SCALE: NONE DRAWN BY: AMB

DATE: MARCH 18, 2005 CHECKED BY: TGB

04/29/2005 02:46:46 PM