F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	11
STA. 1200+00.00	TO STA. 1365+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* (1516.1, 1717 & 1818) R-9				62695

SUMMARY OF QUANTITIES

H01 — H05

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE								100% CITY
				DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
40600895	CONSTRUCTING TEST STRIP	EACH	2		2							
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	145		145							
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	29		29							
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	2576	2576								
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	15900	15900								
42001300	PROTECTIVE COAT	SQ YD	33363	26107	7256							
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	540		540							
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	88		88							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3415	1799	1616							
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	649		649							
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	6023		6023							
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	3516		3516							
44000100	PAVEMENT REMOVAL	SQ YD	24568	13374	11194							
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	326		326							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	23935	15188	8721							26
44000600	SIDEWALK REMOVAL	SQ FT	8580		8580							
44000700	APPROACH SLAB REMOVAL	SQ YD	450		450							
44001980	CONCRETE BARRIER REMOVAL	FOOT	938	938								
44003100	MEDIAN REMOVAL	SQ FT	241		241							
44004250	PAVED SHOULDER REMOVAL	SQ YD	8296	6654	1642							
44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	542	510	32							
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	SQ YD	560	491	69							
48300600	PORTLAND CEMENT CONCRETE SHOULDERS 11"	SQ YD	752.1	752.1								
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	126.2		126.2							
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1							1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1							1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1								1	
50102400	CONCRETE REMOVAL	CU YD	1							1		
50104650	SLOPE WALL REMOVAL	SQ YD	43							43		
50200100	STRUCTURE EXCAVATION	CU YD	13811	260	72					7087	6392	
* 50200410	ROCK EXCAVATION FOR STRUCTURES (SPECIAL)	CU YD	27	27								
50300225	CONCRETE STRUCTURES	CU YD	5452	49	32					3645	1726	

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 2 OF 13

SCALE: NONE — DRAWN BY: JPA

DATE: MARCH 25, 2005 — CHECKED BY: MPG

D:\02373\road\cf7\bsqf7.dsf\02340g1
05/09/2005 04:39:57 PM