F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	12

STA. 1200+00.00 TO STA. 1365+00

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

* (1516.1, 1717 & 1818) R-9

62695

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE (H01)							(H03)	100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	784								784	
	50300260	BRIDGE DECK GROOVING	SY YD	1943								1943	
	50300300	PROTECTIVE COAT	SY YD	13196		36					10463	2697	
	50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24								24	
	50300510	RUSTICATION FINISH	SQ FT	34916		32					34884		
	50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	713938							2770	711168	
	50500505	STUD SHEAR CONNECTORS	EACH	15144							10212	4932	
*	50700209	UNTREATED TIMBER LAGGING	SQ FT	40859							40859		
*	50700211	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	3698							3698		
*	50700213	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	FOOT	79							79		
*	50700215	FURNISHING SOLDIER PILES (W SECTION)	FOOT	31247							31247		
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	852040	11690	14600					482530	343220	
	50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	11							11		
	51100100	SLOPE WALL, 4 INCH	SQ YD	11							11		
	51205200	TEMPORARY SHEET PILING	SQ FT	5040								5040	
	51500100	NAME PLATES	EACH	1								1	
	5421D012	PIPE CULVERTS, CLASS D, TYPE 1 12" (TEMPORARY)	FOOT	85	85								
	550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	5368	5368								
	550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	270	270								
	550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	1397	1397								
	550A0400	STORM SEWERS, CLASS A, TYPE 2, 21"	FOOT	34	34								
	550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	1184	1184								
	550A0420	STORM SEWERS, CLASS A, TYPE 2, 27"	FOOT	1370	1370								
	550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	310	310								
	550A0450	STORM SEWERS, CLASS A, TYPE 2, 36"	FOOT	1466	1466								
	550A0470	STORM SEWERS, CLASS A, TYPE 2, 42"	FOOT	126	126								
	550A0640	STORM SEWERS, CLASS A, TYPE 3, 12"	FOOT	437	437								
	550A0660	STORM SEWERS, CLASS A, TYPE 3, 15"	FOOT	8	8								
	550A0680	STORM SEWERS, CLASS A, TYPE 3, 18"	FOOT	1041	1041								
	550A0700	STORM SEWERS, CLASS A, TYPE 3, 21"	FOOT	432	432								
	550A0710	STORM SEWERS, CLASS A, TYPE 3, 24"	FOOT	719	719								
	550A0720	STORM SEWERS, CLASS A, TYPE 3, 27"	FOOT	516	516								

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 3 OF 13

SCALE: NONE | DRAWN BY: JPA

DATE: MARCH 25, 2005 | CHECKED BY: MPG

05/09/2005 04:39:58 PM

p:\02373\vcad\cf\bsf\03sqty.dgn