F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	14

STA. 1200+00.00 TO STA. 1365+00

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

* (1516.1, 1717 & 1818) R-9

62695

SUMMARY OF QUANTITIES

H01 H05

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE								100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
	60255500	MANHOLES TO BE ADJUSTED	EACH	58	16	42							
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4								
	60260100	INLETS TO BE ADJUSTED	EACH	4	4								
	60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	4								
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2		2							
	60406520	FRAMES AND LIDS, OPEN LID (CITY OF CHICAGO)	EACH	5		5							
	60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	5		5							
	60500040	REMOVING MANHOLES	EACH	8	8								
	60500050	REMOVING CATCH BASINS	EACH	50	49	1							
	60500060	REMOVING INLETS	EACH	95	95								
	60500105	FILLING MANHOLES	EACH	3	3								
	60600605	CONCRETE CURB, TYPE B	FOOT	172.0		40.0	132.0						
	60602200	CONCRETE GUTTER	FOOT	1214.0	1214.0								
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	993.0	520.0	473.0							
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	126.5		126.5							
	60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	51.0		51.0							
	60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	739.5	714.0	25.5							
	60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	641.6	571.6	70.0							
	60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	7366	7366								
*	63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	138	113	25							
*	63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	3	1	2							
*	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	3	1							
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)	EACH	5	5								
	63200310	GUARDRAIL REMOVAL	FOOT	806	154	652							
	63700805	CONCRETE BARRIER TRANSITION	FOOT	142	142								
	66400305	CHAIN LINK FENCE, 6'	FOOT	2992	630	2362							
	66410300	CHAIN LINK FENCE REMOVAL	FOOT	9270	1661	7609							
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	25001	25001								
*	66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1								
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	6	6								
	67100100	MOBILIZATION	L SUM	1	1								
	70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1							

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES

SHEET 5 OF 13

SCALE: NONE DRAWN BY: JPA

DATE: MARCH 25, 2005 CHECKED BY: MPG

P:\02373\road\ci7\dsgn\7dsn03.dgn 05/09/2005 04:39:59 PM