F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	15
STA. 1200+00.00	TO STA. 1365+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-9

62695

SUMMARY OF QUANTITIES

H01 — H05

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE								100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	2		2							
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60		60							
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1250		1250							
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	17970	11870	6100							
	70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	293		293							
	70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	19784		19784							
	70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	1100		1100							
	70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	2112	808	1304							
	70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	202		202							
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	12424	5151	7273							
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	20340	14020	6320							
	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	6686	6366	320							
*	72000100	SIGN PANEL - TYPE 1	SQ FT	50		16				34			
*	72000200	SIGN PANEL - TYPE 2	SQ FT	189						189			
*	72000300	SIGN PANEL - TYPE 3	SQ FT	4606						4606			
	72100100	SIGN PANEL OVERLAY	SQ FT	72						72			
*	72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	9						9			
*	72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	1119						1119			
*	72400720	RELOCATE SIGN PANEL- TYPE 2	SQ FT	20						20			
ΔΔ *	72700100	STRUCTURAL STEEL SIGN SUPPORT-BREAKAWAY	POUND	3547						3547			
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	18						18			
*	72900100	METAL POST, TYPE A	FOOT	165	165								
*	72900200	METAL POST, TYPE B	FOOT	197	197								
*	73000100	WOOD SIGN SUPPORT	FOOT	395						395			
*	73000105	WOOD SIGN SUPPORT, SPECIAL	FOOT	34				34					
*	73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2						2			
*	73300100	OVERHEAD SIGN SUPPORT STRUCTURE - SPAN, TYPE I-A (4'-0" X 4'-6")	FOOT	86						86			
*	73300200	OVERHEAD SIGN SUPPORT STRUCTURE - SPAN, TYPE II-A (4'-6" X 5'-3")	FOOT	418						418			
*	73300300	OVERHEAD SIGN SUPPORT STRUCTURE - SPAN, TYPE III-A (5'-0" X 7'-0")	FOOT	93						93			
*	73302190	OVERHEAD SIGN SUPPORT STRUCTURE - CANTILEVER, TYPE III-C-A (24" X 7'-0")	FOOT	149						149			
*	73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	173						173			
*	73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	475						475			

ΔΔ - SFTY-3C

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 6 OF 13

SCALE: NONE — DRAWN BY: JPA

DATE: MARCH 25, 2005 — CHECKED BY: MPG

p:\02373\road\dist\06\36.dgn

5/06/2005 04:40:20 PM