F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	907	21
STA. 1200+00.00	TO STA. 1365+00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-9

62695

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE (← H01 → ← H05 →)								100% CITY
					DAN RYAN J000-2A	FRONT. RD I000-2A	LIGHTING Y030-1E	I.T.S. Y032-1F	SIGNALS Y031-1F	SIGNING Y002-1C	RETAINING WALLS Y007	76TH ST. BRIDGE X771-2A	LANDSCAPE Y003
	X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	5145.5	5145.5								
	X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	5086.0	4167.5	918.5							
	X6065740	CONCRETE MEDIAN SURFACE, 5 INCH (MODIFIED)	SQ FT	14493		14493							
	X6370920	CONCRETE BARRIER, SINGLE FACE, 32 INCH HEIGHT	FOOT	478	478								
	X6370930	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	420	420								
	X6640210	TEMPORARY CHAIN LINK FENCE (PORTABLE)	FOOT	14693		14693							
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	15	15								
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1								
	X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	330	330								
	X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	144	72	72							
	X7040600	FURNISH TEMPORARY CONCRETE BARRIER	FOOT	460	250	210							
*	X8100060	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL, PVC COATED	FOOT	48					48				
*	X8110125	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., GALVANIZED STEEL, PVC COATED	FOOT	1100					1100				
*	X8150200	TRENCH AND BACKFILL WITH SCREENINGS	FOOT	845			735			110			
*	X8210451	LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 400 WATT, 240 VOLT	EACH	9					9				
*	X8210453	LUMINAIRE, STREET LIGHTING, HIGH PRESSURE SODIUM VAPOR, 400 WATT, 240 VOLT, INSTALL ONLY	EACH	6			6						
*	X8420090	REMOVE EXISTING SIGN LUMINAIRES	EACH	10			10						
*	X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4					4				
*	X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	11					11				
*	X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2					2				
*	X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2					2				
*	X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6					6				
* □	X8810620	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	3					3				
* □	XX004046	AERIAL CABLE REMOVAL	FOOT	370			370						
□	XX005128	STRIP SEAL EXPANSION JOINT ASSEMBLY	FOOT	167								167	
* □	XX005489	STEEL CASINGS, 48"	FOOT	129	129								
□	XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	6343		6343							
□	Z0002600	BAR SPLICERS	EACH	164								164	
*	Z0008236	DRILLED SHAFT IN SOIL 36"	FOOT	430		108					322		
*	Z0008342	DRILLED SHAFT IN ROCK 42"	FOOT	10						10			
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5							
	Z0018800	BRIDGE DRAINAGE SYSTEM	L SUM	1								1	

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 12 OF 13

SCALE: NONE | DRAWN BY: JPA

DATE: MARCH 25, 2005 | CHECKED BY: MPG

05/09/2005 04:40:04 PM

pw:\\pw02373\Project\Cook\70450\70450\sht\25qty.dgn