

62746

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90		COOK	82	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
■ (1012, 1214, 1415, & 1517) RS-3				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 100% STATE I000				
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	176	176				
40600300	AGGREGATE (PRIME COAT)	TON	880	880				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	99	99				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	617	617				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	67	67				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	1000	1000				
42001300	PROTECTIVE COAT	SQ YD	3420	3420				
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	132373	132373				
44000011	BITUMINOUS SURFACE REMOVAL 4"	SQ YD	267310	267310				
44000119	BITUMINOUS REMOVAL OVER PATCHES 4 3/4"	SQ YD	3760	3760				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	10250	10250				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	60	60				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3200	3200				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	200	200				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	300	300				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	79900	79900				
55039700	STORM SEWERS TO BE CLEANED	FOOT	21555	21555				
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1				
60260100	INLETS TO BE ADJUSTED	EACH	10	10				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	205	205				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	348	348				
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	40	40				
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	110	110				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	13	13				
63200310	GUARDRAIL REMOVAL	FOOT	650	650				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		ROADWAY 100% STATE I000				
67100100	MOBILIZATION	L SUM	1	1				
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1				
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	219	219				
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	131871	131871				
70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	31902	31902				
70300550	PAVEMENT MARKING TAPE, TYPE III 8"	FOOT	37306	37306				
70300560	PAVEMENT MARKING TAPE, TYPE III 12"	FOOT	4836	4836				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	24955	24955				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	131871	131871				
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	31902	31902				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	41418	41418				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6629	6629				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	158	158				
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	31902	31902				
78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	466	466				
* 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	62726	62726				
* 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	31902	31902				
* 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	41418	41418				
* 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	6629	6629				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3226	3226				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3226	3226				
* 81016400	CONDUIT IN TRENCH, 1 1/4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	100	100				
* 81016600	CONDUIT IN TRENCH, 2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	100	100				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
KENNEDY EXPRESSWAY

Rev.

PLOT DATE: 4/28/2005