

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-0571	COOK	47	2
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		
				62796

**GENERAL NOTES:**

**ROADWAY:**

- UTILITY LOCATIONS SHOWN ON THESE PLANS MAY NOT BE CORRECT OR COMPLETE. THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE RESPECTIVE UTILITIES OF THE CITY OF CHICAGO. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "CUAN" (CHICAGO UTILITY ALERT NETWORK) AT (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED). CONTACT THE DEPARTMENT OF WATER MANAGEMENT PERMIT SECTION AT (312) 747-7893 FOR WATER AND SEWER LOCATIONS.
- 10 FOOT TRANSITION LENGTHS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS AND GUTTERS AND MEDIANS IN THE FIELD UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ADJUTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS. THE ENGINEER OR AN AUTHORIZED SURVEYOR AGENT WILL WITNESS OR OTHERWISE REFERENCE AND RESET MONUMENTS AS NECESSARY. ALL PROPERTY CORNERS EXCEPT THOSE WITHIN AREAS WHERE THE SCHEDULE, IF PROVIDED, SHOWS PLACEMENT OF R.O.W. MARKERS SHALL REMAIN UNDISTURBED.
- ALL ELEVATIONS SHOWN ARE BASED ON THE CHICAGO CITY DATUM. THE CONVERSION EQUATION FROM CCD TO NAVD 88 IS: NAVD 88 ELEVATION = CCD + 579.19.
- THE CONTRACTOR SHALL COORDINATE ALL ACTIVITIES WITH:
  - CONTRACT 62586 - 57TH STREET BRIDGE - FRONTAGE ROAD, RETAINING WALLS, AND RAMPS (59TH STREET TO 47TH STREET)
  - CONTRACT 62693 - RETAINING WALLS AND FRONTAGE ROAD PAVEMENT (63RD TO 59TH STREET)
  - CONTRACT 62798 - FRONTAGE ROAD SIGNING (59TH TO 47TH)
  - CONTRACT 62799 - FRONTAGE ROAD PERMANENT PAVEMENT MARKING
  - CONTRACT 62801 - TRAFFIC SIGNALS (57TH ST)
  - CONTRACT 62802 - TRAFFIC SIGNALS (55TH ST)
  - CONTRACT 62803 - TRAFFIC SIGNALS (51ST ST)
  - CONTRACT 62804 - TRAFFIC SIGNALS (47TH ST)
  - CONTRACT 62807 - CITY OF CHICAGO LIGHTING (WENTWORTH AVE)
  - CONTRACT 62809 - SEWER AND PAVING (WENTWORTH AVE 53RD TO 51ST)
  - CONTRACT 62811 - SEWER AND PAVING (WENTWORTH AVE 51ST TO 47TH)
  - CONTRACT 62812 - SEWER AND PAVING (51ST ST INTERSECTIONS)
  - CONTRACT 62814 - SEWER AND PAVING (WENTWORTH AVE 57TH TO 59TH)
  - CONTRACT 62835 - SIDEWALK AND DRIVEWAYS - WELLS STREET AND WENTWORTH AVENUE FROM 59TH STREET TO 63RD STREET
  - CONTRACT 62839 - TRAFFIC SIGNALS - 59TH STREET TO 63RD STREET AT WENTWORTH AVENUE AND WELLS STREET.
- THE CONTRACTOR SHALL USE DIMENSIONS SHOWN ON PLANS AS A GUIDE. PROPOSED SIDEWALK SHALL CLOSELY MATCH THE EXISTING WIDTHS OF SIDEWALK AND SHALL NOT BE REDUCED UNLESS DIRECTED OR APPROVED BY THE ENGINEER.
- NO EARTHWORK QUANTITIES HAVE BEEN PROVIDED IN THIS CONTRACT. THE CONTRACTOR IS TO COORDINATE WITH OTHER DAN RYAN ADVANCED WORK CONTRACTS AS STATED ABOVE TO ENSURE THE SUBGRADE IS AT THE CORRECT ELEVATIONS BEFORE PLACEMENT OF SAND CUSHION AND CONCRETE SIDEWALK. SHAPING AND GRADING PAY ITEM HAS BEEN INCLUDED TO PROVIDE PAYMENT FOR FINE GRADING OF THE SUBGRADE IF NECESSARY. THIS CONTRACT DOES NOT INCLUDE QUANTITIES FOR THE PAY ITEMS "SOIL STABILIZERS" AND "APPLYING DUST SUPPRESSION AGENTS". IT HAS BEEN DETERMINED THAT THE PAY ITEM IS NOT NEEDED FOR THE WORK ASSOCIATED WITH THIS CONTRACT. IF THE ENGINEER DETERMINES THAT THIS WORK IS NECESSARY, PAYMENT SHALL BE MADE IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.

**LANDSCAPING:**

- THE CONTRACTOR SHALL USE CARE IN GRADING OR EXCAVATING NEAR ANY AND ALL EXISTING ITEMS WHICH WILL NOT BE REMOVED. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PLANT MATERIAL FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS.
- THE PAY ITEMS TOPSOIL FURNISH AND PLACE, 4" AND SODDING, SALT TOLERANT ARE INCLUDED FOR PLACEMENT AFTER REMOVAL OF PORTLAND CEMENT CONCRETE SIDEWALK FORMWORK. THESE PAY ITEMS SHALL BE USED AS NEEDED AND AS DIRECTED BY THE ENGINEER.

**DRAINAGE AND UTILITIES:**

- IN CASE OF DAMAGE TO CITY OF CHICAGO SEWERS, PRIVATE AND PUBLIC DRAINS, SEWER STRUCTURES AND/OR BENCH MONUMENTS, THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE DEPARTMENT OF WATER MANAGEMENT AT 312-747-7000.
- BENCH MONUMENT LOCATIONS WITHIN THE LIMITS OF THE IMPROVEMENT CAN BE OBTAINED FROM THE DEPARTMENT OF WATER MANAGEMENT AT 1000 EAST OHIO, JARDINE WATER PURIFICATION PLANT, CHICAGO, IL 60611.
- THE RESIDENT ENGINEER AND THE CONTRACTOR SHALL FIELD-VERIFY THE CITY'S EXISTING SEWER FACILITIES INCLUDING PUBLIC AND PRIVATE DRAIN CONNECTIONS IN THE LIMITS OF THE SUBJECT PROJECT FOR ANY CONFLICTS DUE TO THE PROPOSED IMPROVEMENTS. ANY CONFLICTS SHOULD BE RESOLVED WITH THE DEPARTMENT OF WATER MANAGEMENT PRIOR TO THE START OF CONSTRUCTION.
- EXTREME CAUTION IS TO BE TAKEN TO ENSURE THAT NO FACILITY OWNED AND MAINTAINED BY THE DEPARTMENT OF WATER MANAGEMENT IS DAMAGED DURING CONSTRUCTION. IF ANY DAMAGE OCCURS TO ANY FACILITIES, THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE COST OF REPAIRING OR REPLACING THEM.
- WATER SERVICE BOXES, WATER VALVES AND DOMESTIC METER BOXES SHALL BE ADJUSTED TO AN ELEVATION FLUSH WITH THE PROPOSED SIDEWALKS. THE PAY ITEMS "DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED", "WATER VALVES TO BE ADJUSTED", AND "DOMESTIC METER VAULTS TO BE ADJUSTED" HAVE BEEN PROVIDED FOR THESE ADJUSTMENTS. QUANTITIES FOR THE PAY ITEMS DOMESTIC METER VAULTS TO BE ADJUSTED AND WATER VALVES TO BE ADJUSTED WERE NOT DETERMINED BY SURVEY, BUT WERE ESTIMATED FROM SIMILAR PROJECTS. QUANTITIES FOR DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED WERE ASSUMED TO BE ONE PER EACH PROPERTY. THESE PAY ITEMS SHALL BE USED AS NEEDED AND AS DIRECTED BY THE ENGINEER.

**PROJECT COMMITMENTS:**

- IDOT WILL CONTINUE TO COORDINATE WITH THE CITY OF CHICAGO DEPARTMENT OF TRANSPORTATION (CDOT) AND THE CHICAGO TRANSPORTATION AUTHORITY (CTA) USING THE "DAN RYAN EXPRESSWAY LANDSCAPE GUIDELINES", PREPARED BY CDOT AS GUIDELINES THROUGHOUT PHASE II OF THE PROJECT (PREPARATION OF CONTRACT PLANS) ON THE AESTHETICS AND LANDSCAPING TREATMENTS.
- THE ILLINOIS STATE GEOLOGICAL SURVEY (ISGS) CONDUCTED A PRELIMINARY ENVIRONMENTAL SITE ASSESSMENT (PESA) IN WHICH THEY ASSESSED A HIGH RISK FOR THE OCCURRENCE OF HAZARDOUS MATERIALS. A SPECIAL WASTE WAIVER HAS BEEN APPROVED WHICH ALLOWS DESIGN APPROVAL TO BE GRANTED PRIOR TO THE COMPLETION OF SPECIAL WASTE STUDIES. THERE ARE STILL OUTSTANDING SPECIAL WASTE ISSUES THAT MUST BE ADDRESSED. THE ENVIRONMENTAL STUDIES UNIT SHOULD BE CONTACTED AT (847) 705-4101 TO DISCUSS THESE ISSUES. TO DETERMINE THE IMPLICATIONS OF FUTURE DESIGN CHANGES, PLEASE REFER TO THE PESA REVIEW COVER MEMOS FOR ISGS #1106A, AS DEPICTED IN EXHIBIT 7 - SPECIAL WASTE WAIVER IN THE CLASS OF ACTION DETERMINATION (ECAD).

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 90/94 (DAN RYAN EXPRESSWAY) 59th ST TO 47th ST (WENTWORTH AVE SIDEWALKS)
NAME	DATE	
		GENERAL NOTES AND PROJECT COMMITMENTS

SCALE: NONE      DRAWN BY: PHP  
DATE: MARCH 4, 2005      CHECKED BY: MS/JAL



m:\p\04-05-04\CHICAGO\c19\add\_c19\c19\general\909201\20a.rvt 04/05/2005 04:56:23 PM