F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-0571	COOK	47	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

62796

SIDEWALK ITEMS

STATION TO STATION		SAND CUSHION, 3-INCH	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	TOPSOIL FURNISH AND PLACE, 4"	SODDING, SALT TOLERANT	CAST IN PLACE TACTILE/ DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES
		CU YD	SQ YD	SQ FT	SQ YD	SQ YD	SQ FT
WENTWORTH AVENUE	SHEET						
131+44.62 TO 133+00.00	1	5	72	478	19	19	
133+00.00 TO 138+00.00	2	25	335	2,613	101	101	
138+00.00 TO 143+00.00	3	24	317	2,526	97	97	15
143+00.00 TO 148+00.00	4	32	377	3,396	132	132	16
148+00.00 TO 153+00.00	5	28	369	2,949	104	104	
153+00.00 TO 158+00.00	6	31	372	3,249	80	80	48
158+00.00 TO 163+00.00	7	27	339	2,864	115	115	
163+00.00 TO 168+00.00	8	25	394	2,621	97	97	38
168+00.00 TO 173+00.00	9	28	334	3,004	106	106	18
173+00.00 TO 178+00.00	10	28	358	2,936	104	104	23
178+00.00 TO 183+00.00	11	25	375	2,676	94	94	39
183+00.00 TO 188+00.00	12	23	318	2,433	106	106	16
188+00.00 TO 193+00.00	13	23	278	2,401	107	107	
193+00.00 TO 198+00.00	14	26	333	2,800	107	107	
198+00.00 TO 203+00.00	15	28	333	3,000	111	111	
203+00.00 TO 208+00.00	16	26	324	2,727	107	107	
208+00.00 TO 212+25.49	17	27	314	2,828	88	88	22
TOTALS		431	5,543	45,501	1,675	1,675	235

DRIVEWAY AND ALLEY SCHEDULE

	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	PORTLAND CEMENT CONCRETE ALLEY PAVEMENT, 8"	CONCRETE CURB TYPE B	CONCRETE MEDIAN, TYPE SB-6.12	SUB-BASE GRANULAR MATERIAL, TYPE B 4"
WENTWORTH AVENUE	FOOT	SQ YD	SQ YD	FOOT	SQ FT	SQ FT
132+47.25		19				19
135+09.15		23				23
135+98.88		11				11
136+34.98		11				11
138+69.00		14				14
139+94.52		12				12
142+24.86		10				10
148+00.18		25				25
150+15.95		16				16
153+73.76		11				11
158+46.76		21				21
164+42.32	39		53		86	53
167+56.95			29	16		29
175+67.21			30	18		30
180+16.31			29	19		29
182+17.10			44	27		44
184+94.19		24				24
186+45.64		24				24
188+22.30		11				11
195+27.74		22				22
206+17.79		21				21
TOTALS	39	275	185	80	86	460

CTE ENGINEERS
CONSOER TOWNSEND ENVIRODYNE ENGINEERS, INC.
303 EAST WACKER DRIVE, SUITE 600
CHICAGO ILLINOIS 60601-5212, PHONE: (312) 938-0300

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
59th ST TO 47th ST (WENTWORTH AVE SIDEWALKS)

SCHEDULE OF QUANTITIES

SCALE: NONE DRAWN BY: LC
DATE: MARCH 4, 2005 CHECKED BY: JAL

m:\p40468\chl\14-cnt-9add_cnt\9b2\sht\schedules\ss-9b2012s.sht
02/24/2005 04:57:44 PM