

SUMMARY OF QUANTITIES

URBAN  
90% FED.  
10% STATE

CODE NO.	ITEM	UNIT	QUANTITY	ROADWAY
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	19,212	19,212
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2,295	2,295
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14,202	14,202
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	11,285	11,285
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,403	2,403
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,234	2,234
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,352	1,352
78008200	POLYUREA PAVEMENT MARKING TYPE 1 - LETTERS AND SYMBOLS	SO FT	2,295	2,295
78008210	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4"	FOOT	14,202	14,202
78008230	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 6"	FOOT	11,285	11,285
78008240	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8"	FOOT	2,403	2,403
78008250	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 12"	FOOT	2,234	2,234
78008270	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 24"	FOOT	1,352	1,352
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1

0-4000

PAVEMENT MARKING SCHEDULE

STATION TO STATION	SHEET	PAVEMENT MARKING TYPE 1					
		LETTERS AND SYMBOLS	LINE 4"	LINE 6"	LINE 8"	LINE 12"	LINE 24"
<b>WENTWORTH AVENUE</b>		SO FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
131+44.62 TO 133+00.00	1	-	40	-	-	-	-
133+00.00 TO 148+50.00	2	-	945	391	-	93	70
148+50.00 TO 164+00.00	3	223	1,203	1,293	827	449	155
164+00.00 TO 179+50.00	4	-	388	84	-	-	15
179+50.00 TO 195+00.00	5	39	1,696	510	-	203	66
195+00.00 TO 209+00.00	6	-	707	65	260	73	-
209+00.00 TO 212+37.70	7	163	1,544	513	441	462	59
SUB-TOTALS		425	6,523	2,856	1,528	1,280	365
<b>WELLS STREET</b>							
534+86.88 TO 536+50.00	1	39	40	150	-	-	42
536+50.00 TO 552+00.00	2	-	1,081	325	-	119	55
552+00.00 TO 567+50.00	3	331	803	2,004	485	349	152
567+50.00 TO 583+00.00	4	-	294	148	174	110	29
583+00.00 TO 598+50.00	5	116	1,535	819	-	187	88
598+50.00 TO 612+00.00	6	-	589	63	216	81	14
612+00.00 TO 616+75.14	7	223	791	996	-	78	111
SUB-TOTALS		709	5,133	4,505	875	924	491
<b>47TH STREET BRIDGE</b>							
47TH STREET BRIDGE	8	541	680	1,824	-	-	146
<b>51ST STREET BRIDGE</b>							
51ST STREET BRIDGE	8	155	1,106	457	-	30	74
<b>55TH STREET BRIDGE</b>							
55TH STREET BRIDGE	8	310	243	1,102	-	-	225
<b>57TH STREET BRIDGE</b>							
57TH STREET BRIDGE	8	155	517	541	-	-	51
SUB-TOTALS		1,161	2,546	3,924	0	30	496
<b>TOTALS</b>		2,295	14,202	11,285	2,403	2,234	1,352



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
F.A.I. 90/94 (DAN RYAN EXPRESSWAY)  
59th ST TO 47th ST (FRONTAGE RD AND RAMPS)

SUMMARY OF QUANTITIES  
SCHEDULE OF QUANTITIES

SCALE: NONE  
DATE: March 4, 2005

DRAWN BY: SDH  
CHECKED BY: NJH

8:07:39 AM  
3/4/2005