

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-094 1	COOK	40	2
STA.	TO STA.			
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
62835				

GENERAL NOTES:

ROADWAY:

- UTILITY LOCATIONS ON THESE PLANS MAY NOT BE CORRECT OR COMPLETE, THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE RESPECTIVE UTILITIES OF THE CITY OF CHICAGO. BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "CUAN" (CHICAGO UTILITY ALERT NETWORK) AT 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOUR NOTIFICATION IS REQUIRED). CONTACT THE DEPARTMENT OF WATER MANAGEMENT PERMIT SECTION AT (312) 747-7893 FOR WATER AND SEWER LOCATIONS.
- 10 FOOT TRANSITION LENGTHS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS AND GUTTERS AND MEDIANS IN THE FIELD UNLESS OTHERWISE SHOWN. THE TRANSITIONS SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.
- THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.
- WHEN ARTIFICIAL LIGHTING IS USED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY SAFETY PRECAUTIONS TO PROTECT AND PROVIDE ACCESS TO ADJUTTING PROPERTY, UTILITIES, PEDESTRIANS, AND VEHICULAR TRAFFIC.
- WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS. THE ENGINEER OR AN AUTHORIZED SURVEYOR AGENT WILL WITNESS OR OTHERWISE REFERENCE AND RESET MONUMENTS AS NECESSARY. ALL PROPERTY CORNERS EXCEPT THOSE WITHIN AREAS WHERE THE SCHEDULE, IF PROVIDED, SHOWS PLACEMENT OF R.O.W. MARKERS SHALL REMAIN UNDISTURBED.
- ALL ELEVATIONS SHOWN ARE BASED ON THE CHICAGO CITY DATUM. THE CONVERSION FACTOR FROM CCD TO NAVD 88 IS: NAVD 88 ELEVATION = CCD + 579.19.
- THE CONTRACTOR SHALL COORDINATE ALL ACTIVITIES WITH:
 - CONTRACT 62586 - 57TH STREET BRIDGE - FRONTAGE ROAD, RETAINING WALLS, AND RAMPS (59TH STREET TO 47TH STREET)
 - CONTRACT 62693 - RETAINING WALLS AND FRONTAGE ROAD PAVEMENT (63RD STREET TO 59TH STREET)
 - CONTRACT 62795 - SIDEWALK AND DRIVEWAYS (WELLS STREET 59TH STREET TO 47TH STREET)
 - CONTRACT 62796 - SIDEWALK AND DRIVEWAYS (WENTWORTH AVENUE 59TH STREET TO 47TH STREET)
 - CONTRACT 62798 - FRONTAGE ROAD SIGNING (59TH STREET TO 47TH STREET)
 - CONTRACT 62799 - FRONTAGE ROAD PAVEMENT MARKING (59TH STREET TO 47TH STREET)
 - CONTRACT 62806 - CITY OF CHICAGO LIGHTING (WELLS STREET 59TH STREET TO 47TH STREET)
 - CONTRACT 62807 - CITY OF CHICAGO LIGHTING (WENTWORTH AVENUE 59TH STREET TO 47TH STREET)
 - CONTRACT 62813 - SEWER AND PAVING (WELLS STREET 57TH TO 59TH)
 - CONTRACT 62814 - SEWER AND PAVING (WENTWORTH AVE 57TH TO 59TH)
 - CONTRACT 62836 - FRONTAGE ROAD SIGNING (63RD STREET TO 59TH STREET)
 - CONTRACT 62837 - FRONTAGE ROAD PAVEMENT MARKING (63RD STREET TO 59TH STREET)
 - CONTRACT 62839 - TRAFFIC SIGNALS - 59TH STREET AT WENTWORTH AVENUE AND WELLS STREET
 - CONTRACT 62840 - TRAFFIC SIGNALS - 63RD STREET AT WENTWORTH AVENUE AND WELLS STREET
 - CONTRACT 62841 - SEWER TELEVISIONING (63RD STREET TO 59TH STREET)
 - CONTRACT 62842 - CONDUIT AND LIGHT POLE FOUNDATIONS (63RD STREET TO 59TH STREET)
- THE CONTRACTOR SHALL USE DIMENSIONS SHOWN ON PLANS AS A GUIDE. PROPOSED SIDEWALK SHALL CLOSELY MATCH THE EXISTING WIDTHS OF SIDEWALK AND SHALL NOT BE REDUCED UNLESS DIRECTED OR APPROVED BY THE ENGINEER.
- NO EARTHWORK QUANTITIES HAVE BEEN PROVIDED IN THIS CONTRACT. THE CONTRACTOR IS TO COORDINATE WITH OTHER DAN RYAN ADVANCED WORK CONTRACTS AS STATED ABOVE TO ENSURE THE SUBGRADE IS AT THE CORRECT ELEVATIONS BEFORE PLACEMENT OF SAND CUSHION AND CONCRETE SIDEWALK. SHAPING AND GRADING PAY ITEM HAS BEEN INCLUDED TO PROVIDE PAYMENT FOR FINE GRADING OF THE SUBGRADE IF NECESSARY.
- THIS CONTRACT DOES NOT INCLUDE QUANTITIES FOR THE PAY ITEMS "SOIL STABILIZERS" AND "APPLYING DUST SUPPRESSION AGENTS". IT HAS BEEN DETERMINED THAT THESE ITEMS ARE NOT NEEDED FOR THE WORK ASSOCIATED WITH THIS CONTRACT. IF THE ENGINEER DETERMINES THAT THIS WORK IS NECESSARY, PAYMENT SHALL BE MADE IN ACCORDANCE WITH ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
- CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES SHALL BE INSTALLED AT ALL RAMP LOCATIONS, INCLUDING ALLEYS.

DRAINAGE AND UTILITIES

- IN CASE OF DAMAGE TO CITY OF CHICAGO SEWERS, PRIVATE AND PUBLIC DRAINS, SEWER STRUCTURES AND/OR BENCH MONUMENTS, THE CONTRACTOR SHALL IMMEDIATELY CONTACT THE DEPARTMENT OF WATER MANAGEMENT AT 312-747-7000.
- BENCH MONUMENT LOCATIONS WITHIN THE LIMITS OF THE IMPROVEMENT CAN BE OBTAINED FROM THE DEPARTMENT OF WATER MANAGEMENT AT 1000 EAST OHIO, JARDINE WATER PURIFICATION PLANT, CHICAGO, IL 60611.
- THE RESIDENT ENGINEER AND THE CONTRACTOR SHALL FIELD-VERIFY THE CITY'S EXISTING SEWER FACILITIES INCLUDING PUBLIC AND PRIVATE DRAIN CONNECTIONS IN THE LIMITS OF THE SUBJECT PROJECT FOR ANY CONFLICTS DUE TO THE PROPOSED IMPROVEMENTS. ANY CONFLICTS SHOULD BE RESOLVED WITH THE DEPARTMENT OF WATER MANAGEMENT PRIOR TO THE START OF CONSTRUCTION.
- EXTREME CAUTION IS TO BE TAKEN TO ENSURE THAT NO FACILITY OWNED AND MAINTAINED BY THE DEPARTMENT OF WATER MANAGEMENT IS DAMAGED DURING CONSTRUCTION. IF ANY DAMAGE OCCURS TO ANY FACILITIES, THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE COST OF REPAIRING OR REPLACING THEM.
- DOMESTIC METER VAULTS, DOMESTIC WATER SERVICE BOXES AND WATER VALVES SHALL BE ADJUSTED TO AN ELEVATION FLUSH WITH THE PROPOSED SIDEWALKS. THE PAY ITEMS "DOMESTIC METER VAULTS TO BE ADJUSTED", "DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED" AND "WATER VALVES TO BE ADJUSTED" HAVE BEEN PROVIDED FOR THESE ADJUSTMENTS TO BE USED AS NEEDED AND AS DIRECTED BY THE ENGINEER.

LANDSCAPING:

- THE CONTRACTOR SHALL USE CARE IN GRADING OR EXCAVATING NEAR ANY AND ALL EXISTING ITEMS WHICH WILL NOT BE REMOVED. ANY DAMAGE DONE TO EXISTING ITEMS BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT THE CONTRACTOR'S OWN EXPENSE.
- THE CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS FOR THE PROTECTION OF EXISTING PLANT MATERIAL FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF EXISTING PLANT MATERIAL AND THE REPAIR OR REPLACEMENT OF EXISTING PLANT MATERIAL DAMAGED BY THE CONTRACTOR SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF SECTION 201 OF THE STANDARD SPECIFICATIONS.
- IN ADDITION TO AREAS SHOWN ON THE PLANS, THE PAY ITEMS TOPSOIL FURNISH AND PLACE, 4" AND SODDING, SALT TOLERANT ARE INCLUDED FOR PLACEMENT AFTER REMOVAL OF PORTLAND CEMENT CONCRETE SIDEWALK FORMWORK. THESE PAY ITEMS SHALL BE USED AS NEEDED AND AS DIRECTED BY THE ENGINEER.

PROJECT COMMITMENTS:

- IDOT WILL CONTINUE TO COORDINATE WITH THE CITY OF CHICAGO DEPARTMENT OF TRANSPORTATION (CDOT) AND THE CHICAGO TRANSPORTATION AUTHORITY (CTA) USING THE "DAN RYAN EXPRESSWAY LANDSCAPE GUIDELINES", PREPARED BY CDOT AS GUIDELINES THROUGHOUT PHASE II OF THE PROJECT (PREPARATION OF CONTRACT PLANS) ON THE AESTHETICS AND LANDSCAPING TREATMENTS.
- THE ILLINOIS STATE GEOLOGICAL SURVEY (ISGS) CONDUCTED A PRELIMINARY ENVIRONMENTAL SITE ASSESSMENT (PESA) IN WHICH THEY ASSESSED A HIGH RISK FOR THE OCCURRENCE OF HAZARDOUS MATERIALS. A SPECIAL WASTE WAIVER HAS BEEN APPROVED WHICH ALLOWS DESIGN APPROVAL TO BE GRANTED PRIOR TO THE COMPLETION OF SPECIAL WASTE STUDIES. THERE ARE STILL OUTSTANDING SPECIAL WASTE ISSUES THAT MUST BE ADDRESSED. THE ENVIRONMENTAL STUDIES UNIT SHOULD BE CONTACTED AT (847) 705-4101 TO DISCUSS THESE ISSUES. TO DETERMINE THE IMPLICATIONS OF FUTURE DESIGN CHANGES, PLEASE REFER TO THE PESA REVIEW COVER MEMOS FOR ISGS #1106A, AS DEPICTED IN EXHIBIT 7 - SPECIAL WASTE WAIVER IN THE CLASS OF ACTION DETERMINATION (ECAD).



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63rd ST TO 59th ST (SIDEWALKS & DRIVEWAYS)
 GENERAL NOTES AND PROJECT COMMITMENTS

SCALE: NONE
 DATE: MARCH 04, 2005

DRAWN BY: JB
 CHECKED BY: RMG

03/01/2005 10:47:43 AM