

ROADWAY ITEMS

STATION TO STATION	SHEET	PCC SIDEWALK, 5 INCH	SAND CUSHION, 3 INCH	TOPSOIL, FURNISH AND PLACE, 4"	SODDING, SALT TOLERANT	PROTECTIVE COAT	GRADING AND SHAPING ROADWAY	CAST IN PLACE TACTILE/DETECTABLE WARNING SURFACE SYSTEM FOR RAMPS FOR PEOPLE WITH DISABILITIES
		SQ FT	CU YD	SQ YD	SQ YD	SQ YD	UNIT	
WENTWORTH AVENUE								
100+00.10 TO 103+00.00	19	1,922	18	86	86	263	3	0
103+00.00 TO 108+00.00	20	2,621	24	5	5	398	5	16
108+00.00 TO 113+00.00	21	2,183	20	32	32	331	5	29
113+00.00 TO 118+00.00	22	2,610	24	5	5	344	5	39
118+00.00 TO 123+00.00	23	2,660	25	0	0	362	5	0
123+00.00 TO 128+00.00	24	2,603	24	0	0	342	5	28
128+00.00 TO 131+93.21	25	4,891	45	42	42	601	4	38
SUB-TOTALS		19,490	181	170	170	2,641	32	150
WELLS STREET								
506+92.81 TO 511+50.00	26	4,100	38	171	171	541	5	69
511+50.00 TO 516+50.00	27	624	6	16	16	69	5	0
516+50.00 TO 521+75.00	28	2,806	26	218	218	334	5	71
521+75.00 TO 526+75.00	29	2,625	24	101	101	332	5	74
526+75.00 TO 531+75.00	30	2,623	24	81	81	291	5	53
531+75.00 TO 535+32.53	31	2,270	21	53	53	285	4	52
SUB-TOTALS		15,048	139	640	640	1,852	29	319
TOTALS		34,538	320	810	810	4,493	61	469

ALLEY AND DRIVEWAY SCHEDULE

STATION	PCC DRIVEWAY PAVEMENT, 8 INCH	PCC ALLEY PAVEMENT, 8"	CONCRETE CURB TYPE B	SUB-BASE GRANULAR MATERIAL, TYPE B 4"
	SQ YD	SQ YD	FOOT	SQ YD
WENTWORTH AVENUE				
100+52.89	29			29
101+23.84	20			20
105+24.95	55			55
106+08.82	52			52
109+70.96	46			46
110+54.13	42			42
115+01.18	21			21
117+22.33		14	18	14
117+62.25	17			17
118+61.27	19			19
119+57.05	15			15
121+27.25	10			10
122+89.86	22			22
125+13.69	31			31
126+17.16	22			22
131+34.65		15	14	15
131+34.30	41			41
SUB-TOTALS				
	442	29	32	471
WELLS STREET				
507+06.74	31			31
507+07.74	27			27
509+46.40		24	27	24
519+35.08		20	21	20
522+86.58		18	20	18
526+18.99		18	19	18
533+94.64		12	13	12
534+73.51		18	19	18
SUB-TOTALS				
	58	110	119	168
TOTALS				
	500	139	151	639

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2004-094 I	COOK	40	7
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
62835				



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 90/94 (DAN RYAN EXPRESSWAY)
 63rd ST TO 59th ST (SIDEWALKS & DRIVEWAYS)

SCHEDULE OF QUANTITIES

SCALE: NONE DRAWN BY: JB
 DATE: MARCH 04, 2005 CHECKED BY: RMC

03/01/2005 10:48:19 AM