

GENERAL NOTES

ROUTE NO.	SEC.	COUNTY	TOTAL SHEETS	SHEET NO.
FAP 553 (IL 72)	120RS-3	Ogle	145	7
FED ROAD DIST. NO.	ILLINOIS	PROJECT		

Contract #64634

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Commonwealth Edison Co. Verizon
NICOR Gas Co.

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

Mr. Dennis Schultz
IDOT – District 2
819 Depot Ave.
Dixon, IL 61021

Program #5
(Arch. Size)
Enlarge
200%
Enlarge 107%

The applicable portions of Article 105.07 of the Standard Specification shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

CADD data will be available to Contractors and Consultants working on this project. This information will be provided upon request as MicroStation CADD files and Geopak coordinate geometry files ONLY. If data is required in other formats it will be your responsibility to make these conversions. If any discrepancy or inconsistency arises between the electronic data and the information on the hard copy, the information on the hard copy should be used. Contact the District's Project Engineer to request these files.

The removal of raised median, corrugated median, and islands on this project shall include the concrete surface removal, curb & gutter removal, and saw cuts for proposed curb & gutter in the new bituminous overlay.. This work shall be included in the contract unit price per Square Foot for Median Removal.

The removal and disposal of metal pipes without headwalls will not be paid for separately, and shall be included in the contract unit price for Earth Excavation.

Pipe underdrain removal is provided in the plan quantities and shall only be used when the existing pipe underdrains interfere with the installation of the new pipe underdrains or as directed by the Engineer.

Delineators shall be installed as shown in Standard 635001, except that the post shall be rotated 180° and only metal-backed delineators shall be permitted.

Delineators shall be placed at the ends of approach guardrail terminal sections, and at each headwall or end section of AR Culverts. This work shall be included in the cost of EARTH EXCAVATION.

Permanent Survey Markers, Type II shall be cast-in-place as shown on Highway Standard 667101.

The Contractor shall submit to the Engineer a description of location, elevation, and coordinates for each permanent survey marker. The Engineer shall submit this information to the Survey Crew.